

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM			100% FED	
				ROADWAY 1000	BRIDGE X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	99	99	
20100500	TREE REMOVAL, ACRES	ACRE	0.18	0.18	
20101000	TEMPORARY FENCE	FOOT	330	330	
20200100	EARTH EXCAVATION	CU. YD.	135	135	
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	45	45	
20400800	FURNISHED EXCAVATION	CU. YD.	1755	1755	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU. YD.	91		91
20800150	TRENCH BACKFILL	CU. YD.	6	6	
25000210	* SEEDING, CLASS 2A	ACRE	1.00	1.00	
25100630	EROSION CONTROL BLANKET	SQ. YD.	4352	4352	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	360	360	
28000400	PERIMETER EROSION BARRIER	FOOT	1329	1329	
28100107	STONE RIPRAP, CLASS A4	SQ. YD.	976		976
28100108	STONE RIPRAP, CLASS A4 (SPECIAL)	SQ. YD.	366		366
28200200	FILTER FABRIC	SQ. YD.	976		976
35101400	AGGREGATE BASE COURSE, TYPE B	TON	164	164	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	78	78	
40600990	TEMPORARY RAMP	SQ. YD.	58	58	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	178	178	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	116	116	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	29	29	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ. YD.	86	86	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ. FT.	1229	1229	
44000100	PAVEMENT REMOVAL	SQ. YD.	142	142	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ. YD.	1345	1345	
44000600	SIDEWALK REMOVAL	SQ. FT.	619	619	
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ. YD.	1269	1269	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM			100% FED	
				ROADWAY 1000	BRIDGE X071-2A
50157300	PROTECTIVE SHIELD	SQ. YD.	394		394
50157307	PROTECTIVE SHIELD, SPECIAL	L SUM	1	1	
50200100	STRUCTURE EXCAVATION	CU. YD.	191		191
50300225	CONCRETE STRUCTURES	CU. YD.	213.3		213.3
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	323.5		323.5
50300260	BRIDGE DECK GROOVING	SQ. YD.	784		784
50300280	CONCRETE ENCASEMENT	CU. YD.	6		6
50300285	FORM LINER TEXTURED SURFACE	SQ. FT.	3981		3981
50300300	PROTECTIVE COAT	SQ. YD.	960		960
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L. SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3927		3927
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	93050		93050
50800515	BAR SPLICERS	EACH	811		811
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	1350		1350
51202305	DRIVING PILES	FOOT	1350		1350
51203200	TEST PILE METAL SHELLS	EACH	4		4
51204650	PILE SHOES	EACH	28		28
51205200	TEMPORARY SHEET PILING	SQ. FT.	461		461
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	56		56
54200427	PIPE CULVERTS, TYPE 1 RCCP 12"	FOOT	28	28	
54213447	END SECTIONS 12"	EACH	1	1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD.	65		65
60100945	PIPE DRAINS 12"	FOOT	104	104	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	152		152
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1FRAME, CLOSED LID	EACH	1	1	
60605519	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.36	FOOT	63	63	
60900340	TYPE D INLET BOX, STANDARD 609001(SPECIAL)	EACH	2	2	

\* SPECIALTY ITEM

FILE NAME =	USER NAME = \$USER\$	DESIGNED - JDS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 82 OVER HENNEPIN CANAL SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 638	SECTION 129BR-3	COUNTY HENRY	TOTAL SHEETS 73	SHEET NO. 4
\$FILEL\$		DRAWN - WLL	REVISED -					CONTRACT NO. 64B08				
	PLOT SCALE = \$SCALE\$	CHECKED - RJA	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS		AID PROJECT		
	PLOT DATE = \$DATE\$	DATE -	REVISED -									