

SUMMARY OF QUANTITIES				80% FED 20% STATE	80% FED 20% STATE	
CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY QUANTITY I000	BRIDGE QUANTITY X131	SAFETY CODE
50300255	CONCRETE SUPERSTRUCTURE	CU YD	731.0		731.0	
50300260	BRIDGE DECK GROOVING	SQ YD	2,410		2,410	
50300300	PROTECTIVE COAT	SQ YD	3,160		3,160	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	6,615		6,615	
50800105	REINFORCEMENT BARS	POUND	58,930		58,930	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	291,970		291,970	
50800515	BAR SPLICERS	EACH	1,626		1,626	
51100100	SLOPE WALL 4 INCH	SQ YD	100		100	
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	3,000		3,000	
51205100	TEMPORARY SHEET PILING	L SUM	1	1		
51205200	TEMPORARY SHEET PILING	SQ FT	3,000		3,000	
51500100	NAME PLATES	EACH	2	1	1	
51603000	DRILLED SHAFT IN SOIL	CU YD	216.3		216.3	
51604000	DRILLED SHAFT IN ROCK	CU YD	71.6		71.6	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	144		144	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18		18	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	9		9	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	36		36	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	18		18	
52100560	ANCHOR BOLTS, 2"	EACH	18		18	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	65	65		
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	74	74		
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	51	51		
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	92	92		

SUMMARY OF QUANTITIES				80% FED 20% STATE	80% FED 20% STATE	
CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY QUANTITY I000	BRIDGE QUANTITY X131	SAFETY CODE
5421D030	PIPE CULVERTS, CLASS D, TYPE 1 30" (TEMPORARY)	FOOT	24	24		
54213450	END SECTIONS 15"	EACH	4	4		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	89	89		
55037800	STORM SEWERS TO BE CLEANED 12"	FOOT	120	120		
58700300	CONCRETE SEALER	SQ FT	2,200		2,200	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	150		150	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	170		170	
60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1		
60244110	INLETS, SPECIAL, WITH TYPE 9 FRAME AND GRATE	EACH	1	1		
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1	1		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	44.7	44.7		
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	799	799		
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	925.0	925.0		
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	1,414	1,414		
63500105	DELINEATORS	EACH	24	24		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9		
66600205	RE-ERECTING RIGHT-OF-WAY MARKERS	EACH	5	5		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4	4		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		

△

* SPECIALITY ITEMS
 △ NON-PARTICIPATING 100% STATE

HOH		HARRY O. HEFFER ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS		51 East Jackson Blvd. Suite 800 Chicago, IL 60604 312-348-8131	PROJECT NUMBER 2945
F.A.P. RTE. 301	SECTION 21 VBR	COUNTY STEPHENSON	TOTAL SHEETS 112	SHEET NO. 6	
SCALE: NONE			SHEET NO. 2 OF 3 SHEETS		CONTRACT NO. 64D15
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 20
SUMMARY OF QUANTITIES

FILE NAME =	USER NAME = #USER#	DESIGNED - AAF	REVISED -
H:\Project\2945\DGNS\09285507\285507S0.dgn		DRAWN - AAF	REVISED -
	PLOT SCALE = 28.0000' / IN.	CHECKED - BAP	REVISED -
	PLOT DATE = 8/7/2009	DATE - 8/7/2009	REVISED -