

SUMMARY OF QUANTITIES			TOTAL QUANTITY	80% FED 20% STATE ROADWAY QUANTITY 1000	80% FED 20% STATE BRIDGE QUANTITY X131-2A
CODE	ITEM	UNIT			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,097	2,097	
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	38,996	38,996	
70300645	TEMPORARY PAINT PAVEMENT MARKING - LINE 12"	FOOT	400	400	
70300660	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	53	53	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,132	14,132	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,900	2,900	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,110	2,110	
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	219	219	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	25,162	25,162	
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1,353	1,353	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,173	1,173	
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	55	55	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	214	214	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	22	22	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,834	2,834	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	41	41	
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1	1	
* A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5	

SUMMARY OF QUANTITIES			TOTAL QUANTITY	80% FED 20% STATE ROADWAY QUANTITY 1000	80% FED 20% STATE BRIDGE QUANTITY X131-2A
CODE	ITEM	UNIT			
* A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5	
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4		4
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	16	16	
X0712400	TEMPORARY PAVEMENT	SQ YD	5,941	5,941	
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	4,388	4,388	
Z0005400	BREAKER-RUN CRUSHED STONE	TON	1,312	1,312	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	989	989	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	5	5	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	3	3	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

FILE NAME = H:\Pr-jcts\2945\DCNS\1\9205507\20550750.dgn	USER NAME = #USER*	DESIGNED - AAF	REVISED -
		DRAWN - AAF	REVISED -
	PLOT SCALE = 20.0000 "/ IN.	CHECKED - BAP	REVISED -
	PLOT DATE = 8/7/2009	DATE - 8/7/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

* SPECIALITY ITEMS
NON-PARTICIPATING 100% STATE

US ROUTE 20
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 3 SHEETS STA. N/A TO STA. N/A

HOH		HARRY O. HEFFER ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS		56 East Jackson Blvd. Suite 600 Chicago, IL 60604 312-346-9331	PROJECT NUMBER 2945
F.A.P. RTE. 301	SECTION 21 VBR	COUNTY STEPHENSON	TOTAL SHEETS 112	SHEET NO. 7	
FED. ROAD DIST. NO. ILLINOIS			FED. AID PROJECT CONTRACT NO. 64D15		