

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IL 84	1.21B-2M	HENRY and ROCK ISLAND	23	2
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

CONTRACT 64E18

SUMMARY OF QUANTITY

CODE NO.	ITEM	UNIT	100% STATE QUANTITY SFTY-2A
42001300	PROTECTIVE COAT	SQ YD	185
50102400	CONCRETE REMOVAL	CU YD	63
50300255	CONCRETE SUPERSTRUCTURE	CU YD	72
50300530	FLOOR DRAIN EXTENSION	EACH	62
52000212	FINGER PLATE EXPANSION JOINT, 4"	FOOT	180
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10300
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	16,880
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	5870
78300105	PAVEMENT MARKING REMOVAL	FOOT	5810
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2600
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2600
50800515	BAR SPLICERS	EACH	120
X0321781	MECHANICAL SPLICE	EACH	196
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	195
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM

GENERAL NOTES

- Pavement Marking shall be done according to Standard 780001, except as follows: 1. All words, such as ONLY, shall be 2.4 m (8 feet) high.
2. All non-freeway arrows shall be the large size.
3. The distance between yellow no-passing lines shall be 200 mm (8"), not 180 mm (7") as shown in the detail of Typical Lane and Edge Lines.

DESIGNED	M.H.
CHECKED	P.B.
DRAWN	C.L.
CHECKED	M.H./P.B.

SUMMARY OF QUANTITIES
IL ROUTE 84 OVER ROCK RIVER
FAP ROUTE 595 (IL 84), SECTION 1.21B-2-M
HENRY COUNTY
STATION 189+44
STRUCTURE NO. 037-0128

SCALE: DATE: July, 2009
Soodan Soodan & Associates, Inc.
100 North LaSalle Street, Suite 1800
Chicago, Illinois 60602