

SUMMARY OF QUANTITIES

PAY CODE #	LONG DESCRIPTION	UNITS	QUANTITIES	100% STATE	
				ROADWAY J000	BRIDGE SFTY-2A
25100630	EROSION CONTROL BLANKET	SQ YD	45.00	45.00	
28000400	PERIMETER EROSION BARRIER	FOOT	150.00	150.00	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	374.00	374.00	
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	374.00	374.00	
50102400	CONCRETE REMOVAL	CU YD	427.20		427.20
50104650	SLOPE WALL REMOVAL	SQ YD	11.70		11.70
50157300	PROTECTIVE SHIELD	SQ YD	6,123.00		6,123.00
50300255	CONCRETE SUPERSTRUCTURE	CU YD	611.60		611.60
50300260	BRIDGE DECK GROOVING	SQ YD	1,479.00		1,479.00
50300300	PROTECTIVE COAT	SQ YD	2,224.00		2,224.00
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.00		1.00
50500505	STUD SHEAR CONNECTORS	EACH	4,312.00		4,312.00
50501110	STRUCTURAL STEEL REMOVAL	POUND	155,620.00		155,620.00
50501130	STRUCTURAL STEEL REPAIR	POUND	211,520.00		211,520.00
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1.00		1.00
50800105	REINFORCEMENT BARS	POUND	10,108.00	10,108.00	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	167,320.00		167,320.00
51100100	SLOPE WALL 4 INCH	SQ YD	11.70		11.70
52000110	PREFORMED JOINT STRIP SEAL	FOOT	1,636.00		1,636.00
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	100.00		100.00
59200100	BRIDGE WASHING	EACH	1.00		1.00
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	1,398.00	1,398.00	
63700805	CONCRETE BARRIER TRANSITION	FOOT	20.00	20.00	
63801205	TEMPORARY MODULAR GLARE SCREEN	FOOT	1,200.00	1,200.00	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16.00		16.00
67100100	MODILIZATION	L SUM	1.00		1.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	5.00	5.00	
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1.00	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	1.00	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1.00	1.00	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	172.00	172.00	

• SPECIALITY ITEMS

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\FWIDOT\CUSHMANBW\d0149192\d0149192-9409-sht:schedule.dgn		DRAWN -	REVISED -			80	(81-16) M-4	ROCK ISLAND	75	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64F31					
PLOT DATE = Thu Sep 17 13:13:51 2009		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: SHEET NO. OF SHEETS STA. TO STA.