

SCHEDULE OF QUANTITIES

| | | | | | | | | | |
|----------|---|------------------------|----|------------|---|--|--|--|--|
| 25100630 | EROSION CONTROL BLANKET | | | | | | | | |
| | SQ YD | LOCATION | | | | | | | |
| | 45.00 | 16 + 69 | to | 17 + 20 | SLOPE WALL - STATE OF IOWA | | | | |
| | 45.00 | TOTAL | | | | | | | |
| 28000400 | PERIMETER EROSION BARRIER | | | | | | | | |
| | FOOT | LOCATION | | | | | | | |
| | 150.00 | 16 + 69 | to | 17 + 20 | SLOPE WALL - STATE OF IOWA | | | | |
| | 150.00 | TOTAL | | | | | | | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | | | | | | | | |
| | SQ YD | LOCATION | | | | | | | |
| | 373.33 | 1492 + 00 | to | 1497 + 60 | REMARKS 6' wide, see special provision | | | | |
| | 373.33 | TOTAL | | | | | | | |
| 48203005 | HOT-MIX ASPHALT SHOULDERS, 2" | | | | | | | | |
| | SQ YD | LOCATION | | | | | | | |
| | 373.33 | 1492 + 00 | to | 1497 + 60 | REMARKS SEE GENERAL NOTES FOR MIX DESIGN | | | | |
| | 373.33 | TOTAL | | | | | | | |
| 50800105 | REINFORCEMENT BARS | | | | | | | | |
| | POUNDS | LOCATION | | | | | | | |
| | 10108.00 | 1492 + 00 | | 1497 + 60 | REMARKS State of IOWA barrier wall | | | | |
| | 10,108.00 | TOTAL | | | | | | | |
| 63700275 | CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT | | | | | | | | |
| | FOOT | LOCATION | | | | | | | |
| | 1397.50 | STAGE THREE 51 + 72 | | 65 + 69.50 | REMARKS | | | | |
| | 1,397.50 | TOTAL | | | | | | | |
| 63700805 | CONCRETE BARRIER TRANSITION | | | | | | | | |
| | FOOT | LOCATION | | | | | | | |
| | 20.00 | STAGE THREE 51 + 52 | | 51 + 72.00 | REMARKS | | | | |
| | 20.00 | TOTAL | | | | | | | |
| 63801205 | TEMPORARY MODULAR GLARE SCREEN | | | | | | | | |
| | FOOT | LOCATION | | | | | | | |
| | 600.00 | STAGE TWO 1494 + 00 | | 18 + 89.53 | REMARKS IOWA STA 1497+80 = IL STA 16+69.53 | | | | |
| | 600.00 | 82 + 00 | | 88 + 00 | | | | | |
| | 1,200 | TOTAL | | | | | | | |
| 70300625 | TEMPORARY PAINT PAVEMENT MARKING LINE 4" | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | EASTBOUND | | | | | | | |
| | 2225.00 | 1453 + 00 | to | 1475 + 25 | REMARKS Stage I - Yellow inside | | | | |
| | 1025.00 | 75 + 25 | to | 85 + 50 | Stage I - White CL | | | | |
| | 770.00 | 77 + 80 | to | 85 + 50 | Stage I - White outside | | | | |
| | 770.00 | 77 + 80 | to | 85 + 50 | Stage I - Yellow inside | | | | |
| | 1320.00 | 77 + 80 | to | 91 + 00 | Stage I - Yellow, Scenic overlook ramp | | | | |
| | 1440.00 | 1483 + 00 | to | 1497 + 40 | Stage II - Yellow inside | | | | |
| | 601.00 | 55 + 39 | to | 61 + 40 | Stage II - White outside | | | | |
| | 1026.00 | 75 + 24 | to | 85 + 50 | Stage II - White CL | | | | |
| | 770.00 | 77 + 80 | to | 85 + 50 | Stage II - White outside | | | | |
| | 770.00 | 77 + 80 | to | 85 + 50 | Stage II - Yellow inside | | | | |
| | 1320.00 | 77 + 80 | to | 91 + 00 | Stage II - Yellow, Scenic overlook ramp | | | | |
| | 7311.00 | 1483 + 00 | to | 75 + 00 | Stage III - Yellow inside | | | | |
| | 19348.00 | Sub-Totd | | | | | | | |
| | | WESTBOUND | | | | | | | |
| | 2872.00 | 1497 + 00 | to | 44 + 61 | Stage I - White outside | | | | |
| | 3538.00 | 47 + 62 | to | 83 + 00 | Stage I - Yellow inside | | | | |
| | 1618.00 | 77 + 82 | to | 94 + 00 | Stage I - White outside | | | | |
| | 1425.00 | 61 + 65 | to | 75 + 90 | Stage II - White outside | | | | |
| | 2135.00 | 61 + 65 | to | 83 + 00 | Stage II - Yellow inside | | | | |
| | 1618.00 | 77 + 82 | to | 94 + 00 | Stage II - White outside | | | | |
| | 6891.00 | 1491 + 20 | to | 79 + 00 | Stage III - Yellow inside | | | | |
| | 20097.00 | Sub-Totd | | | | | | | |
| | | MISC | | | | | | | |
| | 600.00 | US 67 Eastbound | | | Stage I - Yellow | | | | |
| | 300.00 | US 67 Westbound | | | Stage I - White | | | | |
| | 550.00 | IL 84 Eastbound | | | Stage II - White | | | | |
| | 525.00 | IL 84 Westbound | | | Stage II - Yellow | | | | |
| | 1975.00 | Sub-Totd | | | | | | | |
| | 41,420.0 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|--|-----------|----|---------|--|--|--|--|--|
| 70300635 | TEMPORARY PAINT PAVEMENT MARKING LINE 6" | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | EASTBOUND | | | | | | | |
| | 96.50 | 51 + 53 | to | 55 + 39 | REMARKS Stage II - Turkey tracks, 2' long, 6' between - White | | | | |
| | 96.50 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|---|-----------|----|---------|--|--|--|--|--|
| 70300645 | TEMPORARY PAINT PAVEMENT MARKING LINE 12" | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | WESTBOUND | | | | | | | |
| | 163.93 | 63 + 50 | to | 73 + 20 | REMARKS Stage I - Diagonals, 16.9' long, 100' between - White | | | | |
| | 163.93 | 63 + 50 | to | 73 + 20 | Stage II - Diagonals, 16.9' long, 100' between - White | | | | |
| | 163.93 | 63 + 50 | to | 73 + 20 | Stage III - Diagonals, 16.9' long, 100' between - White | | | | |
| | 491.79 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|----------------------------|-----------|--|-----------|-----------------------------|--|--|--|--|
| 70400100 | TEMPORARY CONCRETE BARRIER | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | STAGE ONE | | | | | | | |
| | 507.5 | 1491 + 93 | | 1497 + 00 | REMARKS IN STATE OF IOWA | | | | |
| | 80.0 | 1497 + 00 | | 1497 + 80 | IN STATE OF IOWA | | | | |
| | 400.0 | 47 + 50 | | 51 + 50 | ILLINOIS | | | | |
| | 748.0 | 51 + 50 | | 59 + 00 | ILLINOIS | | | | |
| | 652.0 | 59 + 00 | | 65 + 52 | ILLINOIS | | | | |
| | 2,387.5 | Sub-Totd | | | | | | | |
| | | STAGE TWO | | | | | | | |
| | 175.0 | 1496 + 05 | | 1497 + 80 | IN STATE OF IOWA | | | | |
| | 32.5 | 16 + 69 | | 17 + 00 | ON BRIDGE | | | | |
| | 3,452.0 | 17 + 00 | | 51 + 52 | ON BRIDGE | | | | |
| | 198.0 | 51 + 52 | | 53 + 50 | ILLINOIS | | | | |
| | 6,245.0 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|-------------------------------------|-----------|--|-----------|-----------------------------|--|--|--|--|
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | STAGE TWO | | | | | | | |
| | 587.5 | 1491 + 80 | | 1497 + 00 | REMARKS IN STATE OF IOWA | | | | |
| | 80.0 | 1497 + 00 | | 1497 + 80 | IN STATE OF IOWA | | | | |
| | 950.0 | 53 + 50 | | 62 + 00 | ILLINOIS | | | | |
| | 1,617.5 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|---|-----------|--|-----------|-------------------------------------|--|--|--|--|
| 70400600 | RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED) | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | STAGE ONE | | | | | | | |
| | 515.5 | 1491 + 88 | | 1497 + 00 | REMARKS DELIVER TO STATE OF IOWA | | | | |
| | 77.5 | 1497 + 00 | | 1497 + 80 | DELIVER TO STATE OF IOWA | | | | |
| | 75.0 | | | | ON BRIDGE | | | | |
| | 62.5 | | | | ON BRIDGE | | | | |
| | 400.0 | 47 + 50 | | 51 + 52 | ILLINOIS ABUTMENT ON BRIDGE | | | | |
| | 1,450.0 | 51 + 52 | | 66 + 02 | ILLINOIS | | | | |
| | 2,580.5 | TOTAL | | | | | | | |

| | | | | | | | | | |
|----------|--|-----------|----|-----------|------------------------------------|--|--|--|--|
| 78008210 | POLYUREA PAVEMENT MARKING TYPE I • LINE 4" | | | | | | | | |
| | EQOI | LOCATION | | | | | | | |
| | | EASTBOUND | | | | | | | |
| | 5780.00 | 1440 + 00 | to | 1497 + 80 | REMARKS Left edge line - Yellow | | | | |
| | 2505.00 | 1440 + 00 | to | 1465 + 05 | Right edge line - White | | | | |
| | 1731.00 | 1474 + 00 | to | 1491 + 31 | Right edge line - White | | | | |
| | 1467.00 | 51 + 53 | to | 66 + 20 | Left edge line - Yellow | | | | |
| | 821.00 | 57 + 99 | to | 66 + 20 | Right edge line - White | | | | |
| | 1930.00 | 66 + 20 | to | 85 + 50 | Left edge line - Yellow | | | | |
| | 163.00 | 66 + 20 | to | 67 + 83 | Right edge line - White | | | | |
| | 14397.00 | Sub-Totd | | | | | | | |
| | | WESTBOUND | | | | | | | |
| | 780.00 | 1490 + 00 | to | 1497 + 80 | Left edge line - Yellow | | | | |
| | 182.00 | 1490 + 00 | to | 1491 + 82 | Right edge line - White | | | | |
| | 1467.00 | 51 + 53 | to | 66 + 20 | Left edge line - Yellow | | | | |
| | 368.00 | 62 + 52 | to | 66 + 20 | Right edge line - White | | | | |
| | 1930.00 | 66 + 20 | to | 85 + 50 | Left edge line - Yellow | | | | |
| | 697.00 | 66 + 20 | to | 73 + 17 | Right edge line - White | | | | |
| | 451.00 | 80 + 99 | to | 85 + 50 | Right edge line - White | | | | |
| | 5875.00 | Sub-Totd | | | | | | | |
| | 20,272.0 | TOTAL | | | | | | | |