

STAGE CONSTRUCTION ITEMS														
LOCATION	LENGTH	TEMPORARY CONCRETE BARRIER FOOT	RELOCATE TEMP CONC BARRIER FOOT	TEMP MODULAR GLARE SCREENS(6) FOOT	TEMPORARY SPBGR, TA FOOT	TBT, T1 (SPECIAL) TANGEANT EACH	HMA(3) SURF REM 8" SQ YD	HMA (3) SHOULDERS 8" SQ YD	WORK ZONE PVT MK REMOVAL(4) SQ FT	PAVEMENT MARKING REMOVAL(5) FOOT	WET TEMP PVT MK TAPE, TYPE III-4"			
											WHITE FOOT	YELLOW FOOT		
STAGE I														
WBL	1408+60 TO 282+00*	41421							13807		41421.0			
	1408+60 TO 1802+25	39365							12122			36365.0		
	1415+00 TO 1802+25	48406**								48406.0				
EBL	1366+00 TO 1802+25	43625							29083		43625.0	43625.0		
	1435+80 TO 1438+30	250			250									
	1411+00 TO 1802+25	39125								39125.0				
	1438+30 TO 1438+80	50				1								
	1615+50 TO 1618+00	250			250									
	1618+00 TO 1618+50	50				1								
	1763+80 TO 1766+30	250			250									
	1766+30 TO 1766+80	50				1								
STAGE II														
EBL	1366+00 TO 1802+19	43619							14540		43619.0			
	1406+35 TO 1802+19	39584							13195			39584.0		
WBL	1408+55 TO 1801+70	39315							13105		39315.0			
	1408+55 TO 288+62*	42028							14009			42028.0		
	1430+80 TO 1431+30	50				1								
	1431+30 TO 1433+80	250			250									
	1609+25 TO 1609+75	50				1								
	1609+75 TO 1612+25	250			250									
	1754+50 TO 1755+00	50				1								
	1755+00 TO 1757+50	250			250									
STAGE I														
	1408+60 TO 1804+25	39565	39565.0			39565								
STAGE II														
	1406+55 TO 1802+19	39364	39364.0			39364.0								
EBL ON 10' SHLD (FOR STAGE I TRAFFIC)														
	1411+00 TO 1802+23(2)	37195					16960	16960						
WBL ON 10' SHLD (FOR STAGE II TRAFFIC)														
	1408+55 TO 1801+70(1)	34865					15495	15495						
TOTALS														
			78,929.0			78,929.0	1500.0	6.0	32455.0	32455.0	96054	87531.0	167980.0	161602.0

\*STA E0 - 1815+21.84(BK) = 275+00(AH)  
\*\*OVERALL LENGTH INCLUDES LENGTH TO REMOVE EXISTING CENTERLINE PVT MK  
(1) LENGTH HERE = ACTUAL LENGTH - LENGTH OF AREAS WHERE THERE WILL BE NEW SHOULDERS NEAR STRUCTURES=4450 LN FT.NO BIT SHOULDER NEEDED FOR NEWLY CONSTRUCTED AREAS NEAR BRIDGES  
(2)LENGTH HERE = ACTUAL LENGTH - LENGTH OF ALL STRUCTURES = 965'  
(3)TO BE PERFORMED PRIOR TO STAGE I CONSTRUCTION  
(4) MK ZONE PVT MK REMOVAL IS TO REMOVE THE WET WATHER TAPE PLACED AFTER STAGE I AND STAGE II CONSTRUCTION  
(5) PAVEMENT MARKING REMOVAL IS TO REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO STAGE I AND STAGE II CONSTRUCTION  
(6) CLARE SCREENS TO BE USEFD DURING STAGE I AND STAGE II CONSTRUCTION-RELOCATION OF GLARE SCREENS INCLUDED IN COST OF RELOCATE TEMP CONC BARRIER  
USE A 24" HEIGHT FOR GLARE SCREENS, SPACED AT 22" CENTERS. MAX. INSTALLATION ANGLE IS 70 DEGREES.

SURFACE REMOVAL-PCC AND HMA				
LOCATION	LENGTH FT	HMA SURF REM VAR. DEPTH* SQ YD	PCC SURF REM- BJ SQ YD	HMA SURF REM- BJ SQ YD
<b>EASTBOUND</b>				
1404+94 TO 1405+64	60.0			267.0
1449+50 TO 1453+52 (SN 006-0127)	400.0	1778.0		
1528+50 TO 1532+50 (SN 006-0132)	400.0	1778.0		
1671+26 TO 1675+26 (SN 006-0129)	400.0	1778.0		
1736+38 TO 1740+38 (SN 006-0133)	400.0	1778.0		
1803+19 TO 1803+89	60.0			267.0
<b>WESTBOUND</b>				
1404+94 TO 1405+64	60.0			267.0
1449+50 TO 1453+52 (SN 006-0127)	400.0	1778.0		
1671+26 TO 1675+26 (SN 006-0129)	400.0	1778.0		
1803+19 TO 1803+79	60.0			267.0
<b>MEDIAN</b>				
WEST X-OVER			1260.0	
EAST X-OVER			1260.0	
<b>GRAND TOTAL</b>		<b>10668.0</b>	<b>2520.0</b>	<b>1068.0</b>

\* UNDER STRUCTURES TO MAINTAIN MINIMUM 16' VERTICAL CLEARANCE

BARRIER WALL MKS SCHEDULE	
LOCATION	BARRIER WALL MARKERS
STA TO STA	EACH
SN 006-0170 AND 006 0171	18
SN 006-0172 AND 006 0173	8
SN 006-0174 AND 006 0175	6
<b>TOTAL</b>	<b>32</b>

Rev. 10-14-09

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\braboypc\10112640\d368	908-sht-detail1.dgn	DRAWN -	REVISED -			I-80	**	BUREAU	344	16	
	PLOT SCALE = 50.7353' / IN.	CHECKED -	REVISED -			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	66908		
	PLOT DATE = Sep 07, 2009 - 02:16:37 PM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					