



DECK SLAB REPAIR (PARTIAL)

DECK PATCHING PLAN

S.N. 006-0127

DECK SURVEY DATE: 07/11/06
COMPLETED BY: DISTRICT

PATCH NO.	DECK SLAB REPAIR (PARTIAL DEPTH)	DECK SLAB REPAIR (FD 11)	DECK SLAB REPAIR (FD 11 2)
	SO. YD.	SO. YD.	SO. YD.
1	0.11		
2	0.22		
3	0.11		
4	0.11		
5	0.44		
6	0.33		
7	0.22		
8	0.67		
9	0.67		
10	0.11		
11	0.44		
12	0.22		
13	0.11		
14	0.11		
15	0.11		
16	0.44		
17	0.44		
18	0.11		
19	0.89		
20	0.22		
21	0.50		
22	0.11		
23	0.44		
24	0.22		
25	0.11		
26	0.11		

(CONTINUED)

27	0.11		
28	0.89		
29	0.44		
30	0.11		
31	0.11		
32	0.22		
33	0.11		
34	0.22		
35	0.67		
36	0.22		
37	0.22		
38	0.11		
39	0.11		
40	0.11		
41	0.11		
42	0.22		
43	0.33		
44	0.33		
45	0.67		
46	0.11		
47	0.22		
48	0.22		
49	0.67		
50	0.11		
51	0.22		
52	0.11		
53	0.22		
54	1.67		
55	0.44		
56	0.11		
57	0.22		
TOTALS	17.20		

TOTAL DECK AREA=
716.95 SQ. YDS.

2.4% PARTIAL DEPTH
PATCHING REQUIRED
ON DECK

**06-[7BR&BR-1,7VB-M,6BR&6,7 RS-1 & I]

FILE NAME =	USER NAME = braboygo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE REPAIR PLANS SN 006-0127	F.A. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw\work\p\dot\braboygo\d0112640\vd36908-sht-details.DGN	PLOT SCALE = 50.7353' / IN.	DRAWN -	REVISED -			I-80	**	BUREAU	344	239	
PLOT DATE = Sep 07, 2009 - 01:48:39 PM	DATE -	CHECKED -	REVISED -			CONTRACT NO. 66908		ILLINOIS FED. AID PROJECT			
		DATE -	REVISED -			SCALE: _____	SHEET NO. ____ OF ____ SHEETS	STA. _____ TO STA. _____			