

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 4 OF 6

LOCATION OF WORK:	FAP 808	FAP 808	FAP 808	FAP 808
	IL RTE. 130	IL RTE. 130	IL RTE. 130	IL RTE. 130
COUNTY:	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE	RURAL TWO LANE
	DOUGLAS	CHAMPAIGN	CHAMPAIGN	CHAMPAIGN
	STA. 297+50.00	STA. 1000+00.00 AH	STA. 1145+38.00	STA. 2224+94.00
	TO	TO		
	STA. 320+90.82 BK	STA. 2309+00.00	S.N. 010-2036	S.N. 010-2035
FUNDING BREAKOUT:	80% FED	80% FED	80% FED	80% FED
	20% STATE	20% STATE	20% STATE	20% STATE
CONSTRUCTION TYPE CODE:	I000	I000	X028-2A	X028-2A

- * (205,57,105)RS-2
- ** CHAMPAIGN & DOUGLAS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2.00		2.00		
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2.00		2.00		
54214509	PRECAST REINFORCED FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	12.00		12.00		
54248510	CONCRETE COLLAR CONCRETE	CU YD	4.00		4.00		
542D0217	PIPE CULVERTS, CLASS D, TYPE 112"	FOOT	176.00		176.00		
542D0220	PIPE CULVERTS, CLASS D, TYPE 115"	FOOT	1250.00		1250.00		
542D0223	PIPE CULVERTS, CLASS D, TYPE 118"	FOOT	1222.00		1222.00		
542D0226	PIPE CULVERTS, CLASS D, TYPE 121"	FOOT	230.00		230.00		
542D0229	PIPE CULVERTS, CLASS D, TYPE 124"	FOOT	1090.00	202.00	888.00		
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	46.00		46.00		
550A0030	STORM SEWERS, CLASS A, TYPE 18"	FOOT	45.00		45.00		
550A0050	STORM SEWERS, CLASS A, TYPE 112"	FOOT	593.00		593.00		
550A0190	STORM SEWERS, CLASS A, TYPE 148"	FOOT	258.00		258.00		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	337.00		337.00		
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	214.00		214.00		
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	84.00		84.00		
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	33.00		33.00		
55100300	STORM SEWER REMOVAL 8"	FOOT	105.00		105.00		
55100500	STORM SEWER REMOVAL 12"	FOOT	14.00		14.00		
55100900	STORM SEWER REMOVAL 18"	FOOT	98.00		98.00		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	13.00		13.00		
60109601	BACKSLOPE DRAINS, TYPE 16"	FOOT	46.00		46.00		
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	31.00	1.00	30.00		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.00		1.00		
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1.00		1.00		
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	3.00		3.00		
60224100	MANHOLES, TYPE A, SPECIAL, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1.00		1.00		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	17.00		17.00		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	18.00		18.00		
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	2.00		2.00		
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2.00		2.00		
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3.00		3.00		
60255500	MANHOLES TO BE ADJUSTED	EACH	1.00		1.00		
60258800	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 8 GRATE	EACH	1.00		1.00		
60260100	INLETS TO BE ADJUSTED	EACH	1.00		1.00		

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Sheet 4 of 6

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 07/31/09 CHECKED BY: G.A.E.

PLOT DATE = 8/17/2009
 FILE NAME = C:\Users\k\p\p\DOT\CEARL\LOCK\JUN\000145\70623-sh4-500.dgn
 PLOT SCALE = 42.3529 / IN.
 USER NAME = ceartockjld