CONTRACT NO. 70623

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (205,57,105)RS-2
** CHAMPAIGN & DOUGLAS

SUMMARY OF QUANTITIES

SHEET 5 OF 6

LOCATION OF WORK:			FAP 808 IL RTE. 130 RURAL TWO LANE	FAP 808 IL RTE. 130 RURAL TWO LANE	FAP 808 IL RTE. 130 RURAL TWO LANE	FAP 808 IL RTE. 130 RURAL TWO LANE
COUNTY:			DOUGLAS	CHAMPAIGN	CHAMPAIGN	CHAMPAIGN
			STA. 297+50.00 TO STA. 320+90.82 BK	STA. 1000+00.00 AH TO STA. 2309+00.00	STA. 1145+38.00 S.N. 010-2036	STA. 2224+94.00 S.N. 010-2035
FUNDING BREAKOUT:			80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
CONSTRUCTION TYPE CODE:			I000	I000	X028-2A	X028-2A
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY
60402210	GRATES, TYPE 8	EACH	5.00		5.00	
60500050	REMOVING CATCH BASINS	EACH	38.00	1.00	37.00	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6.00		6.00	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4122.00		4122.00	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	39604.00	1100.00	38504.00	
61100605	MISCELLANEOUS CONCRETE	CU YD	0.70		0.70	
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	278.00		278.00	
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	274.00	4.00	270.00	
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	137.00		137.00	
61101017	STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	4.00		4.00	
61101020	STORM SEWERS PROTECTED, CLASS A, 18"	FOOT	124.00		124.00	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4.00		4.00	
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	3.00		3.00	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1862.50		1862.50	
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	300.00		300.00	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	125.00		125.00	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	16.00		16.00	
63200310	GUARDRAIL REMOVAL	FOOT	2500.00		2500.00	
63500105	DELINEATORS	EACH	118.00	4.00	114.00	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	183.00	8.00	175.00	
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	6.00		6.00	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12.00	1.00	11.00	
67100100	MOBILIZATION	L SUM	1.00		1.00	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.00	0.10	0.90	
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.00		1.00	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.00	0.10	0.90	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00		1.00	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70.00	2.00	68.00	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14360.00	716.00	13644.00	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109443.00	5342.00	104101.00	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1599.00	80.00	1519.00	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	109443.00	5342.00	104101.00	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	601.00	30.00	571.00	
* 78200405	GUARDRAIL MARKERS	EACH	40.00		40.00	

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Sheet 5 of 6

SCALE: NOT TO SCALE — DRAWN BY: B.B.P.
DATE: 07/31/09 — CHECKED BY: G.A.E.

PLOT DATE = 8/17/2009
FILE NAME = c:\pwidot\projects\PWIDOT\CEARLOCK\D\c000445\70623-sht-500.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = cearlockjd