CONTRACT NO. 70623

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (205,57,105)RS-2
** CHAMPAIGN & DOUGLAS

SCHEDULE OF QUANTITIES – RURAL
DOUGLAS COUNTY

SHEET 4 OF 4

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION	TO	STATION	QUANTITY (EACH)	
297+20.00		320+90.82 (BK)	30.00	
		TOTAL =	30.00	EACH

78100100 RAISED REFLECTIVE PAVEMENT MARKER

STATION	TO	STATION	QUANTITY (EACH)	TYPE
297+20.00		320+90.82 (BK)	30.00	TWO-WAY AMBER
		TOTAL =	30.00	EACH

70300100 SHORT TERM PAVEMENT MARKING

STATION	TO	STATION	APPLY AFTER:	QUANTITY (FT)	COLOR
297+20.00		320+90.82 (BK)	MILLING	240.00	YELLOW
297+45.00		320+90.82 (BK)	LEVEL BINDER	236.00	YELLOW
297+20.00		320+90.82 (BK)	HMA SURFACE	240.00	YELLOW
			TOTAL =	716.00	FT

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

STATION	TO	STATION	QUANTITY (SQ FT)	
297+20.00		320+90.82 (BK)	80.00	
		TOTAL =	80.00	SQ FT

78001110 PAINT PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
297+20.00		320+90.82 (BK)	RT. EDGE LINE	2370.82	WHITE
297+20.00		320+90.82 (BK)	LT. EDGE LINE	2370.82	WHITE
297+20.00		320+90.82 (BK)	SKIP DASH	600.00	YELLOW
			TOTAL =	5341.64	FT
			USE =	5342.00	FT

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
297+20.00		320+90.82 (BK)	RT. EDGE LINE	2370.82	WHITE
297+20.00		320+90.82 (BK)	LT. EDGE LINE	2370.82	WHITE
297+20.00		320+90.82 (BK)	SKIP DASH	600.00	YELLOW
			TOTAL =	5341.64	FT
			USE =	5342.00	FT

63500105 DELINEATORS

STATION	OFFSET (FT)	DELINEATOR TYPE	QUANTITY (EACH)	
306+39.00	30.00 RT.	S.F. / T.A.	1.00	
306+81.00	30.50 LT.	D.F. / T.A.	1.00	
316+05.60	29.00 LT.	S.F. / T.A.	1.00	
318+20.60	28.50 RT.	S.F. / T.A.	1.00	
		TOTAL =	4.00	EACH

S.F. = SINGLE FACE
D.F. = DOUBLE FACE
T.A. = TRIPLE AMBER

#5000901 SIGN AND POST

STATION	OFFSET (FT)	QUANTITY (EACH)	
311+87.00	40.00 LT.	1.00	
	TOTAL =	1.00	EACH

X0326372 REMOVE RIGHT-OF-WAY MARKERS

STATION	OFFSET (FT)	QUANTITY (EACH)	
320+70.00	40.00 LT.	1.00	
	TOTAL =	1.00	EACH

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	OFFSET (FT)	QUANTITY (EACH)	
300+00.00	40.00 LT.	1.00	
305+00.00	40.00 LT.	1.00	
310+00.00	40.00 RT.	1.00	
310+00.00	40.00 LT.	1.00	
315+00.00	40.00 RT.	1.00	
315+00.00	40.00 LT.	1.00	
320+59.70	40.00 LT.	1.00	
320+69.43	70.00 LT.	1.00	
	TOTAL =	8.00	EACH

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES-RURAL
DOUGLAS COUNTY
Sheet 4 of 4

SCALE: N/A
DATE: 06/26/09
DRAWN BY: B.B.P.
CHECKED BY: G.A.E.

PLOT DATE = 9/1/2009
FILE NAME = c:\pw_work\PWIDOT\PIERSONBR\d0l0l445\Y0623-sht-schedule.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = piersonbr