

SCHEDULE OF QUANTITIES – RURAL CHAMPAIGN COUNTY

SHEET 16 OF 27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	*	**	715	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (205,57,105)RS-2 ** CHAMPAIGN & DOUGLAS				

INCIDENTAL HOT-MIX ASPHALT SURFACE SCHEDULE. (CON'T)

STATION	DESCRIPTION	INCIDENTAL AREA (SQ FT)	AVERAGE THICKNESS (INCH)	40800050	40800010	40800030	40600982	44000196	35101400	44000200	40200800	REMARKS
				INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	BIT MAT'L PRIME COAT (GALLONS)	AGGREGATE PRIME COAT (TON)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL - SPECIAL (SQ YD)	AGGREGATE BASE COURSE, TYPE B (TON)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	AGGREGATE SURFACE COURSE, TYPE B (TON)	
LT. 2212+61.80	F.E.									8.00		REMOVE ENTRANCE
LT. 2215+50.00	30' F.E.										31.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2216+30.20	F.E.									10.00		REMOVE ENTRANCE
LT. 2216+42.70	F.E.									8.00		REMOVE ENTRANCE
RT. 2218+54.80	MBTO									28.00		REMOVE MBTO
LT. 2218+68.70	18' P.E.	431.00	2.50	6.70	4.79	0.10		26.00	9.00	9.00	2.00	10 FT BIT / 8 FT AGG
RT. 2222+03.21	T.R. 265B / 700N	2529.00	2.50	39.34	28.10	0.56	72.00	137.00	5.00			IMPROVE TURNING RADIUS
LT. 2222+05.48	T.R. 265B / 700N	2464.00	2.50	38.33	27.38	0.55	64.00	168.00	19.00			IMPROVE TURNING RADIUS
RT. 701+50.00	30' F.E.										16.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2235+31.02	30' F.E.									10.00	34.00	REMOVE APRON / 6" AGG TO ROW
RT. 2235+45.50	30' F.E.									7.00		REMOVE ENTRANCE
RT. 2248+10.00	30' F.E.										34.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2248+44.00	30' F.E.									11.00	34.00	REMOVE APRON / 6" AGG TO ROW
LT. 2255+02.40	30' F.E.									6.00	34.00	REMOVE APRON / 6" AGG TO ROW
RT. 2255+12.90	F.E.									7.00		REMOVE ENTRANCE
LT. 2256+31.60	30' F.E.									23.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 2259+08.00	MBTO									16.00		REMOVE MBTO
LT. 2259+21.90	18' P.E.	435.00	2.50	6.77	4.83	0.10		27.00	9.00	11.00	3.00	10 FT BIT / 15 FT AGG
LT. 2261+95.00	30' F.E.									11.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 2268+34.00	F.E.									5.00		ABANDONED F.E. / REMOVE APRON
LT. 2268+43.00	30' F.E.									10.00	31.00	REMOVE APRON / 6" AGG TO ROW
RT. 2275+01.96	ROOSEVELT RD. / 800 N	2456.00	2.50	38.20	27.29	0.55	69.00	94.00	15.00			IMPROVE TURNING RADIUS
LT. 2275+02.19	ROOSEVELT RD. / 800 N	2514.00	2.50	39.11	27.93	0.56	71.00	56.00	12.00			IMPROVE TURNING RADIUS
RT. 800+78.00	30' F.E.										11.00	NEW ENTRANCE / 6" AGG TO ROW
LT. 2275+90.00	30' F.E.										39.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2279+31.00	F.E.									8.00		REMOVE ENTRANCE
RT. 2279+60.00	30' F.E.										39.00	NEW ENTRANCE / 6" AGG TO ROW
RT. 2281+98.00	14' P.E.	395.00	3.50	8.60	4.39	0.09			8.00	10.00	4.00	10 FT BIT / 15 FT AGG
TOTAL =				996.45	678.81	13.58	2408.00	1078.00	546.00	809.00	1607.00	
USE =				997.00	679.00	13.80	2408.00	1078.00	546.00	809.00	1607.00	
				(TON)	(GALLONS)	(TON)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(TON)	

PLOT DATE = 8/12/2009
 FILE NAME = c:\pwworking\PIERSONBR\d001445\70623-sht16-schedule-champaign.dgn
 USER NAME = pier_sonbr