

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		MCLEAN	310	4
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
		* (57-4)R, HBY, HBR, (57-4)BIDM CONTRACT #70757		

LOCATION OF WORK:

	①	②	③	④	⑤	⑥	⑦	⑧	⑨
	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE

CODE NO.	DESCRIPTION	UNIT	McLean CO. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE																
				J000-2A ROADWAY I-55	I000-2A ROADWAY LINDEN ST.	X271-2A STRUCTURE BUS. RT. 51	X171-2A STRUCTURE S.P.C.S.L.	X271-2A STRUCTURE LINDEN ST.	SFTY-3J STRUCTURE TOWANDA	Y030-1E LIGHTING	Y002-1C SIGNING	Y002-1C SIGNING	Y045 BIKE PATH							
MX032788	CONCRETE BARRIER REMOVAL AND REPLACEMENT	METER	26.0	26.0																
*MX734100	CONCRETE FOUNDATIONS, GROUND MOUNT	CUM	5.0									5.0								
MX033785	TEMPORARY PIPE CULVERT, 375 MM	METER	65.0		65.0															
MX542190	PIPE CULVERTS, TYPE 3, REINFORCED CONCRETE - ARCH, EQUIVALENT ROUND-SIZE 375MM	METER	3.5																	3.5
*MX830150	LIGHT POLE, GALVANIZED STEEL, 12.0M. M.H., 2.4M DAVIT ARM - TWIN	EACH	35.0								35.0									
X0326707	TEMPORARY PROTECTION SYSTEM FOR BICYCLE TRAFFIC	L SUM	1.0			1.0														
MX637140	CONCRETE BARRIER, SINGLE FACE, 865 MM HEIGHT (SPECIAL)	METER	162.0	162.0																
MX033786	GATE VALVE AND BOX, 300MM	EACH	2.0		2.0															
MX033787	DUCTILE IRON SANITARY FORCE MAIN, CLASS 52, WITH POLYETHYLENE ENCASEMENT, 400MM	METER	104.0		104.0															
*MX830155	LIGHT POLE, GALVANIZED STEEL, 12.0M. M.H., 2.4M DAVIT ARM - TWIN (SPECIAL)	EACH	5.0								5.0									
*X0326708	TUNNEL LIGHTING CONTROL SYSTEM	L SUM	1.0								1.0									
*X0326709	TUNNEL LUMINAIRE, 150 WATT HIGH PRESSURE SODIUM VAPOR	EACH	12.0								12.0									
*X0326710	TUNNEL LUMINAIRE, 450 WATT HIGH PRESSURE SODIUM VAPOR	EACH	194.0								194.0									
X0326713	SANITARY SEWER CONNECTION	EACH	2.0		2.0															
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	1.0		1.0															
*X0326711	VIDEO CAMERA CONTROL SYSTEM	L SUM	1.0								1.0									
28000300	TEMPORARY DITCH CHECKS	EACH	21.0		13.0															8.0
28000500	INLET AND PIPE PROTECTION	EACH	76.0	56.0	4.0															16.0
40702700	FURNISH PROFILOGRAPH	L SUM	1.0	1.0																
42101070	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE (VARIABLE)	EACH	6.0	6.0																
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0							1.0										
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0							1.0										
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2.0				2.0													
50105200	REMOVE EXISTING CULVERTS	EACH	15.0	14.0	1.0															
50300100	FLOOR DRAINS	EACH	8.0			4.0				4.0										
50500505	STUD SHEAR CONNECTORS	EACH	9,678.0			336.0				9,342.0										
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1.0			1.0														
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1.0			1.0														
50800515	BAR SPLICERS	EACH	1,442.0							1,442.0										
51203200	TEST PILE METAL SHELLS	EACH	4.0							4.0										
51500100	NAME PLATES	EACH	4.0			2.0				2.0										
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18.0							18.0										

*SPECIALTY ITEMS

8/21/2009
#124

LAYOUT	JAH	
DRAWN	JAH	
REVIEWED	DLR	03/19/04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4)BIDM
MCLEAN COUNTY



JOB NO.
94S2063
DATE
8/21/2009