

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		MCLEAN	310	9
FED. ROAD DIST. NO. (ILLINOIS)		FED. AID PROJECT		
* (57-4JR, HBY, HBR, 157-4VB)DM CONTRACT #70757				

LOCATION OF WORK:

CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	LOCATION OF WORK:										
				1	2	3	4	3	5	6	7	8	9	
				90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	100% STATE	90% FED. 10% STATE	
		CONSTRUCTION TYPE CODE												
		J000-2A ROADWAY I-55	I000-2A ROADWAY LINDEN ST.	X271-2A STRUCTURE BUS. RT. 51	X171-2A STRUCTURE S.P.C.S.L.	X271-2A STRUCTURE LINDEN ST.	SFTY-3J STRUCTURE TOWANDA	Y030-1E LIGHTING	Y002-1C SIGNING	Y002-1C SIGNING	Y045 BIKE PATH			
M4425235	CLASS A PATCHES, TYPE II, 300MM	SQ M	100.0	100.0										
M4425335	CLASS A PATCHES, TYPE III, 300MM	SQ M	100.0	100.0										
M4425435	CLASS A PATCHES, TYPE IV, 300MM	SQ M	100.0	100.0										
M4429200	PATCHING REINFORCEMENT	SQ M	300.0	300.0										
M4429400	SAW CUTS	METER	50.0	50.0										
M4812000	AGGREGATE SHOULDERS, TYPE B	MTON	2,165.0	1,785.0										380.0
M4820400	HOT-MIX ASPHALT SHOULDERS	MTON	860.0		860.0									
M4830300	PORTLAND CEMENT CONCRETE SHOULDERS - 300MM	SQ M	42,495.0	42,495.0										
M4830330	PORTLAND CEMENT CONCRETE SHOULDERS - 330MM	SQ M	9,015.0	9,015.0										
M5010240	CONCRETE REMOVAL	CUM	569.9			86.9	483.0							
M5010465	SLOPE WALL REMOVAL	SQ M	1,707.0			46.0	1,661.0							
M5010570	PROTECTIVE SHIELD	SQ M	796.0			236.0		560.0						
M5020100	STRUCTURE EXCAVATION	CUM	1,023.0			119.0		904.0						
M5030350	CONCRETE STRUCTURES	CUM	508.5			130.8		372.7	5.0					
M5030360	CONCRETE SUPERSTRUCTURE	CUM	619.6			141.9		477.7						
M5030390	BRIDGE DECK GROOVING	SQ M	2,139.0			392.0		1,747.0						
M5030450	PROTECTIVE COAT	SQ M	2,536.0			582.0		1,954.0						
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	127,580.0			26,440.0		100,760.0	380.0					
M5110100	SLOPE WALL 100 MM	SQ M	930.0			40.0		890.0						
M5120128	FURNISHING METAL SHELL PILES 305MM X 4.55MM	METER	216.0			216.0								
M5120129	FURNISHING METAL SHELL PILES 305MM X 6.35MM	METER	858.0					858.0						
M5120176	FURNISHING METAL SHELL PILES 356MM X 6.35MM	METER	462.5					462.5						
M5120335	DRIVING PILES	METER	1,536.5			216.0		1,320.5						
M5120900	TEMPORARY SHEET PILING	SQ M	1,252.4		716.0	106		430.4						
M5200064	PREFORMED JOINT SEAL 64MM	METER	109.7			63.5		46.2						

*SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4JR, HBY, HBR, 157-4VB)DM
MCLEAN COUNTY

REVISIONS	
NAME	DATE



JOB NO.
94S2063
DATE
8/20/2009

8/20/2009
 #1252
 LAYOUT
 DRAWN
 REVIEWED
 JSH
 JSH
 DJH 10/21/04