

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		MCLEAN	310	10
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
		• (57-4)R, HBY, HBR, (57-4)BIDM CONTRACT #70757		

LOCATION OF WORK:

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	90% FED. 10% STATE															
				1	2	3	4	3	5	6	7	8	9						
				JOOO-2A ROADWAY I-55	I000-2A ROADWAY LINDEN ST.	X271-2A STRUCTURE BUS. RT. 51	X171-2A STRUCTURE S.P.C.S.L.	X271-2A STRUCTURE LINDEN ST.	SFTY-3J STRUCTURE TOWANDA	Y030-1E LIGHTING	Y002-1C SIGNING	Y002-1C SIGNING	Y045 BIKE PATH						
M5200225	PREFORMED JOINT STRIP SEAL	METER	16.9			16.9													
M5210022	ANCHOR BOLTS, M24	EACH	148.0			40.0		108.0											
M542E016	END SECTIONS 375MM	EACH	2.0		2.0														
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	4.0																4.0
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	1.0																1.0
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	2.0																2.0
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	1.0																1.0
M542E716	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH, EQUIVALENT ROUND-SIZE 375MM	EACH	2.0																2.0
M542F012	METAL END SECTIONS 300MM	EACH	2.0	2.0															
M542H025	PIPE CULVERTS, CLASS A, TYPE 1375MM	METER	50.1		8.0														42.1
M542M040	PIPE CULVERTS, CLASS A, TYPE 6 600MM	METER	84.5																84.5
M5500030	STORM SEWERS, CLASS A, TYPE 1300MM	METER	1,423.0	1,381.5															41.5
M5500050	STORM SEWERS, CLASS A, TYPE 1450MM	METER	1,331.5	1,266.0															65.5
M5500065	STORM SEWERS, CLASS A, TYPE 1600MM	METER	68.3	68.3															
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	172.5																172.5
M5500485	STORM SEWERS, CLASS A, TYPE 2 900MM	METER	18.0																18.0
M5870300	CONCRETE SEALER	SQM	19.8			19.8													
M6010125	PIPE DRAINS 300MM	METER	36.0	36.0															
M6010605	PIPE UNDERDRAINS 100MM	METER	14,954.0	14,705.0			249.0												
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	808.0	808.0															
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	18.0	18.0															
M6021470	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 20 FRAME AND GRATE	EACH	1.0	1.0															
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2.0																2.0
M6021735	MANHOLES, TYPE A, 1.5M DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2.0																2.0
M6060010	CLASS SI CONCRETE (OUTLET)	CUM	1.0																1.0
M6060015	CLASS SI CONCRETE (INLET)	CUM	0.6																0.6
M6060260	CONCRETE GUTTER, TYPE A *SPECIALTY ITEMS	METER	135.1																135.1

MCLEAN
CO. URBAN

CONSTRUCTION TYPE CODE

8/21/2009 #7189

LAYOUT	JLN	
DRAWN	JLN	
REVIEWED	DLT	03/18/04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4)BIDM
MCLEAN COUNTY



JOB NO.
94S2063
DATE
8/21/2009