

DRAINAGE SCHEDULE I-55

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	-	MCLEAN	310	35
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* (57-4)R, HBY, HBR, (57-4VB)DM CONTRACT #70757				

PIPES											
PIPE NO.	FROM STRUCT.	INVERT	TO STRUCT.	INVERT	PIPE SLOPE (%)	TRENCH BACKFILL (CU M)	PIPE CULVERTS CL A, TY 1 375 mm (METER)	STORM SEWERS, CL A, TY 1 300 mm (METER)	STORM SEWERS, CL A, TY 1 450 mm (METER)	STORM SEWERS, CL A, TY 1 600 mm (METER)	TEMPORARY PIPE CULVERTS 375 mm (METER)
P79	M-90	256.300	M-89	256.030	0.34	34.7			79.8		
P80	M-91	257.044	M-90	256.445	0.75	25.5		79.8			
P82	M-94	258.970	M-93	258.473	1.29	9.1		38.6			
P81A	M-93	258.400	M-93A	258.350	2.50	1.0			2.0		
P81	M-93A	258.308	M-92A	257.282	0.84	39.4			122.5		
P82B	M-92A	257.200	M-92	257.150	2.50	1.0			2.0		
P87	M-100	265.082	M-99	264.542	0.71	21.1		76.5			
P86	M-99	264.542	M-98	263.570	1.27	18.1		76.7			
P85	M-98	263.405	M-97	262.267	1.48	24.6			76.7		
P84A	M-97	262.167	M-97A	262.150	0.85	1.0			2.0		
P84	M-97A	262.050	M-96A	261.228	1.07	24.6			76.7		
P84B	M-96A	261.178	M-96	261.128	2.50	1.0			2.0		
P83	M-96	261.128	M-95	259.990	1.48	24.6			76.7		
P89	M-102	264.850	M-103	264.260	0.75	19.7		79.1			
P90	M-103	264.095	M-104	263.574	0.66	26.6			79.1		
P91	M-104	263.574	M-105	263.475	0.44	8.1			22.6		
P92	M-105	263.475	M-106	263.445	1.08	1.0			2.8		
P93	M-106	263.445	M-107	262.785	2.22	37.8			29.7		
P95	M-109	264.747	M-108	263.859	1.12	19.7		79.1			
P94	M-108	263.859	M-107	263.350	2.45	8.6		20.8			
P99	M-114	271.012	M-113	270.677	0.59	14.2		57.1			
P98	M-113	270.677	M-112	269.569	1.39	19.8		79.7			
P97	M-112	269.569	M-111	267.500	2.59	38.8		79.8			
P96	M-111	267.500	M-110	266.168	1.67	42.9			79.7		
P100	M-115	270.863	M-116	270.399	0.83	17.6		55.8			
P101	M-117	270.186	M-116	270.100	3.58	1.0		2.4			
P102	M-118	269.585	M-119	268.297	2.41	9		53.5			
P103	M-119	268.297	M-120	266.655	2.38	16.3		69.0			
P104	M-120	266.655	M-121	264.685	2.86	16.3		69.0			
P105	M-121	264.685	M-122	262.355	3.38	23.7		69.0			
P106	M-123	259.993	M-124	258.005	2.55	19.6		77.9			
P107	M-124	258.005	M-125	256.380	1.96	25.9		82.9			
P108A	M-125	256.230	M-125A	256.216	0.70	1.0			2.0		
P108	M-125A	256.216	M-126A	255.632	0.70	33.6			82.9		
P108B	M-126A	255.632	M-126	255.618	0.70	1.0			2.0		
P109	M-127	255.453	M-128	255.075	0.57	17.0		66.1			
P109A	M-128	255.000	M-128A	254.950	2.50	1.0			2.0		
P110	M-128A	254.925	M-129A	254.630	0.45	22.4			66.1		
P110A	M-129	254.650	M-129A	254.630	1.00	1.0		2.0			
P111	M-129A	254.630	M-130A	254.290	0.52	21.6			66.1		
P111A	M-130	254.310	M-130A	254.290	1.00	1.0		2.0			
P112	M-130A	254.135	M-131A	254.000	0.20	18.4			66.3		
P112A	M-131A	254.000	M-131	253.980	1.00	1.0			2.0		
P113	M-132	253.776	M-133	253.416	0.50	17.1		72.3			
P113A	M-133	253.295	M-133A	253.275	1.00	1.0			2.0		
P114	M-133A	253.251	M-134A	252.891	0.50	23.2			72.3		
P114A	M-134	252.911	M-134A	252.891	1.00	1.0		2.0			
P115	M-134A	252.891	M-135A	252.531	0.50	23.2			72.3		
P115A	M-135	252.551	M-135A	252.531	1.00	1.0		2.0			
P116	M-135A	252.531	M-136A	251.900	0.88	33.3			72.1		
P116A	M-136A	251.900	M-136	251.880	1.00	1.0			2.0		
P117	M-137	251.926	M-138	251.490	0.53	20.4		82.9			
P117A	M-138	251.420	M-138A	251.400	1.00	1.0			2.0		
P118	M-138A	251.340	M-139A	250.773	0.68	34.2			82.9		
P118A	M-138A	250.957	M-139A	250.937	1.00	1.0		2.0			
P119A	M-139A	250.773	M-141C	250.490	0.68	10.2			40.9		
P119B	M-141C	250.490	M-140A	250.200	0.68	11.8			42.1		
P119C	M-140A	250.460	M-140	250.440	1.00	1.0			2.0		
P119D	M-141B	250.709	M-141C	250.699	0.50	1.0		2.0			
P119E	M-141A	250.716	M-141B	250.709	0.50	1.0		1.5			
LINDEN											
P122	N/A	264.785	N/A	264.750	0.44		8.0				
*P133	N/A	265.175	N/A	264.850	0.50						65.0
BIKE PATH (SEE BIKE PATH DRAINAGE SCHEDULE)							42.1	41.5	65.5		
GRAND TOTALS						894.0	50.1	1,423.0	1,331.5	68.3	65.0

* SEE LINDEN STREET MAINTENANCE OF TRAFFIC STAGE 2&3

NOTE: SEE BIKE PATH DRAINAGE SCHEDULE FOR BIKE PATH DRAINAGE ITEMS.

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 55
SECTION (57-4)R, HBY, HBR, (57-4VB)DM
MCLEAN COUNTY

DRAINAGE SCHEDULE



JOB NO.
94S2063
DATE
6/18/2009

REVISIONS	
NAME	DATE

LAYOUT: J.H. 03/16/04
DRAWN: J.H. 03/16/04
REVIEWED: D.H. 03/18/04
6/18/2009
94S2063