

LOCATION OF WORK: FAP 91(IL 16)  
RURAL  
EDGAR COUNTY  
STA 600+30.00 TO 33366+96.66  
IL 16 FROM COLES/EDGAR LINE TO IL 133 IN PARIS

FUNDING BREAKOUT: FEDERAL--100%  
CONSTRUCTION TYPE CODE: 1000

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,300.0
40600300	AGGREGATE (PRIME COAT)	TON	225.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	101.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	18,920.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	225,165.0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	703.0
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	8.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	477.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	68.0
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	70.0
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	11.0
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	158.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,021.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	4.0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3.0
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	703.0
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	5.0

FILE NAME =	USER NAME = bowerml	DESIGNED - GTR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\PWIDOT\BOWERML\d0112471\7076	text.dgn	DRAWN - BBP	REVISED -						91	(1,2)RS-4 & 3RS-3	EDGAR	23	4
	PLOT SCALE = 40.0000 / IN.	CHECKED - GTR	REVISED -		SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 70763				
	PLOT DATE = 8/7/2009	DATE - 01/06/09	REVISED -		ILLINOIS FED. AID PROJECT								