

LOCATION OF WORK:

MCLEAN COUNTY
 STRUCTURE
 IMPROVEMENT
 SN 057-0073
 FAS 2466 (US 150)
 STA. 236+82.50
 100% STATE
 SFTY-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	QUANTITY
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	67.0
50102400	CONCRETE REMOVAL	CU YD	51.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	51.8
50300300	PROTECTIVE COAT	SQ YD	306.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7,430.0
50800515	BAR SPLICERS	EACH	48.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	220.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1.0
63200310	GUARDRAIL REMOVAL	FOOT	60.0
67100100	MOBILIZATION	L SUM	1.0
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1.0
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,175.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,025.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0

* SPECIALTY ITEM

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\p\work\p\dot\shererjm\d0143296\0579807-shr-500.dgn	DRAWN - JMS	REVISED -	2466					(57-18)BJR	MCLEAN	17	4	
PLOT SCALE = 100.0000 / / IN.	CHECKED -	REVISED -	SCALE: NO SCALE SHEET NO. 1 OF 1 SHEETS					CONTRACT NO. 70807				
PLOT DATE = 8/14/2009	DATE - 073109	REVISED -	ILLINOIS FED. AID PROJECT									