

LOCATION NO.	LOCATION	REBUILD EXISTING SIGNAL HEAD FACE, 1-SECTION, LED (RED)	REBUILD EXISTING SIGNAL HEAD FACE, 1-SECTION, LED (YELLOW)	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED (RED)	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED (YELLOW)	REMOVE EXISTING SIGNAL HEAD	SOLAR POWERED FLASHING BEACON ASSEMBLY (COMPLETE)
1	IL 123 AT IL 125	1	2				
2	US 24 AT 12TH ST.	3	2				
3	US 51 AT IL 16	1					
4	OLD US 36 EAST OF RIVERTON	2	2				
5	IL 48 AT NOKOMIS RD	4	2				
6	US 67 & CAMDEN RD	2	2				
7	OLD 36 AT EAST SIDE OF NEW BERLIN				2	2	
8	IL 106 AT IL 100, DETROIT			1	1	2	
9	US 54 AT SUMMER HILL		1				
10	IL 106 AT US 54, PITTSFIELD WYE	1					
11	US 54 AT IL 96	4					
12	US 24 AT SOUTH JCT IL 96			3		3	
13	US 24 AT NORTH JCT IL 96			2		2	
14	US 24 AT 5TH, QUINCY	2					
15	US 67 / IL 100 / IL 103	8					
16	IL 57 AT IL 96	1					
17	IL 29 AT INDIAN POINT RD		1				
18	IL 121 AT McDONALD STREET, MT. PULASKI		2				
19	IL 16, SCHRAM CITY, WEST		1				
20	IL 16, SCHRAM CITY, EAST		1				
21	OLD 36 AT MT. AUBURN RD	1					
22	US 24 AT EINHAUS RD	2	2				
23	IL 96 AT WARSAW RD	3					
24	IL 4 AT MONTEREY MINE RD		2				
25	IL 4 AT STAUNTON		2				
26	IL 54 AT SPAULDING	1	2				
27	IL 104 AT IL 99	1	1				
28	US 136 AT CONNABLE RD			1	2	3	
29	US 24 AT SPRING LAKE RD		2				
30	IL 54 @ MACDONALD ST, MT. PULASKI						2
31	8TH ST & TAINTOR RD, SPRINGFIELD						4
	TOTAL	37	27	7	5	12	6

GENERAL NOTES:

THE COST OF REPLACING ANY GALVANIZED STEEL CONDUIT IN ORDER TO INSTALL PROPOSED SIGNAL HEADS SHALL BE CONSIDERED INCIDENTAL.

THE PROPOSED SOLAR POWERED FLASHING BEACONS IN MT. PULASKI SHALL BE INSTALLED OVER THE EXISTING SIGNS ON TELESPAR POSTS IN



ADVANCE OF THE MACDONALD STREET INTERSECTION. CONTACT BUREAU OF OPERATIONS (217) 785-5312 FOR FURTHER INFORMATION.

THE PROPOSED SOLAR POWERED FLASHING BEACONS AT 8TH & TAINTOR IN SPRINGFIELD SHALL BE INSTALLED OVER THE EXISTING SIGNS ON



TELESPAR POSTS CONTACT BUREAU OF OPERATIONS (217) 785-5312 FOR FURTHER INFORMATION.

REMOVED EQUIPMENT SHALL BECOME PROPERTY OF THE CONTRACTOR

SUMMARY OF QUANTITIES:

12	EACH	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED
64	EACH	REBUILD EXISTING SIGNAL HEAD FACE, 1-SECTION, LED
12	EACH	REMOVE EXISTING SIGNAL HEAD
6	EACH	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)

• D-6 TRAF SIG MODERN 2008-1

FILE NAME =	USER NAME = coxjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwwork\pwwid\COXJ\dm19058\TS_She	eta.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	DISTR-WIDE	5	4
	PLOT SCALE = 40000.0000' / IN.	CHECKED -	REVISED -		CONTRACT NO. 72A23								
	PLOT DATE = Aug-13-2009 03:09:31PM	DATE -	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT								