



- LEGEND**
- ① EXIST. P.C.C. SIDEWALK 4"
 - ② EXIST. SUB-BASE GRANULAR MATERIAL 4"
 - ③ EXIST. AGGREGATE BASE COURSE 6"
 - ④ EXIST. STABILIZED BASE COURSE, VAR. FR. 0 TO 9"
 - ⑤ EXIST. BITUMINOUS BASE COURSE WIDENING 9"
 - ⑥ EXIST. BITUMINOUS BASE COURSE WIDENING 8"
 - ⑦ EXIST. BITUMINOUS BASE COURSE 10"
 - ⑧ EXIST. BITUMINOUS OVERLAY 7"
 - ⑨ EXIST. BITUMINOUS OVERLAY
 - ⑩ EXIST. CONCRETE GUTTER, TYPE A
 - ⑪ EXIST. BITUMINOUS SHOULDERS 8"
 - ⑫ EXIST. BITUMINOUS SHOULDERS 10"
 - ⑬ EXIST. AGGREGATE SHOULDER, TYPE B
 - ⑭ EXIST. PIPE UNDERDRAIN 4"
 - ⑮ PROP. HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH) *
 - ⑯ PROP. HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"
 - ⑰ PROP. HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"
 - ⑱ PROP. LEVELING BINDER (MACHINE METHOD), N50 3/4"
 - ⑲ PROP. HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 1 1/2"
 - ⑳ PROP. HOT-MIX ASPHALT SHOULDERS
 - ㉑ PROP. AGGREGATE SHOULDERS, TYPE B
 - ㉒ PROP. THERMOPLASTIC PAVEMENT MARKING - LINE 5"
 - ㉓ PROP. PAINT PAVEMENT MARKING - LINE 5"

* NOMINAL MILLING DEPTH 1/2" @ C

FULL S.E.: (S.E.#5 = 2.25%)
 STA 530+37.39 TO 541+26.04
S.E. TRANSITION:
 STA 529+33.91 TO 530+37.39
 STA 541+26.04 TO 542+29.52

- ** NOTE:**
- (A) THE FOLLOWING FR. STA. 505+50.00 TO 505+65.00 SHALL APPLY:
 PROP. THICKNESS OF LEV. BIND. VAR. FR. 0 TO 3/4".
 HMA SURFACE REMOVAL VAR. FR. 0 TO 1/2" AND SHALL BE PAID FOR AS SURFACE REMOVAL (VARIABLE DEPTH).
 PROP. HMA SHOULDER THICKNESS VAR. FR. 1 1/2" TO 2 1/4" AND SHALL BE PAID FOR AS HMA SHLDRS.
 - (B) EXIST. SUB-BASE GRANULAR MATERIAL & BASE COURSE WIDENING AND PROP. SHLDR MILLING & HMA SHLDRS END AT STA. 507+83.00 LT.

FULL S.E.: (S.E.#6 = 2.40%)
 STA 545+42.15 TO 555+87.68
S.E. TRANSITION:
 STA 544+34.47 TO 545+42.15
 STA 555+87.68 TO 556+95.36

(NOT TO SCALE)

FILE NAME =	USER NAME = coxjm	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS			F.A.P. RTE. 777	SECTION 10RS-5	COUNTY Montgomery	TOTAL SHEETS 54	SHEET NO. 9
ct:\pw_work\pwt\dot\coxjm\dms22861\Sh1Typ\2e1.dgn		DRAWN - JWC	REVISED -		SCALE: NTS	SHEET NO. 6 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 72A68			
PLOT SCALE = 106.0000' / IN.		CHECKED - RSC	REVISED -		[ILLINOIS] FED. AID PROJECT							
PLOT DATE = Aug-13-2009 02:27:38PM		DATE -	REVISED -									