

ROADWAY SCHEDULE												
LOCATION STATION TO STATION	LENGTH (FT)	EXIST PAVEMENT WIDTH (FT)	LEV BINDER THICKNESS (IN)	HMA SURF THICKNESS (IN)	HMA SURF REMOVAL BUTT - JOINT (SQ YD)	HMA SURF REMOVAL 1 1/2" (SQ YD)	HMA SURF REMOVAL 2 1/4" (SQ YD)	HMA SURF REMOVAL VAR DPTH (SQ YD)	HMA CONC SURF CSE "C" N50 (TON)	LEV BINDER (MM), N50 (TON)	BIT MAT PRIME COAT (TON)	AGG PRIME COAT (TON)
FAP 777 (IL 185)												
STA. 399+66.92 TO STA. 399+86.92	20.00	26	-	1.5	57.78	-	-	-	-	-	0.02	0.12
STA. 399+66.92 TO STA. 429+64.00	2,997.08	26	-	1.5	-	-	-	-	727.29	-	-	-
STA. 399+86.92 TO STA. 400+01.92	15.00	26	0 to 0.75	-	-	-	-	-	-	0.91	-	-
STA. 399+86.92 TO STA. 429+64.00	2,977.08	26	-	1.5	-	-	-	8,600.45	-	-	3.27	17.20
STA. 400+01.92 TO STA. 429+64.00	2,962.08	26	0.75	-	-	-	-	-	-	359.40	-	-
STA. 429+64.00 TO STA. 430+62.00	98.00	Var fr. 27' to 40'	0.75	1.5	-	-	-	364.78	30.64	15.32	0.14	0.73
STA. 430+62.00 TO STA. 431+65.00	103.00	40	-	1.5	-	-	-	457.78	-	-	0.17	0.92
STA. 430+62.00 TO STA. 435+37.00	475.00	40	0.75	1.5	-	-	-	-	-	177.33	88.67	-
STA. 431+65.00 TO STA. 432+00.00	35.00	40	-	1.5	-	-	-	155.56	-	-	0.06	0.31
STA. 432+00.00 TO STA. 435+37.00	337.00	40	-	1.5	-	-	-	-	-	-	0.57	3.00
STA. 435+37.00 TO STA. 435+87.00	50.00	26	0.75	1.5	-	-	1,497.78	-	-	-	0.05	0.29
STA. 435+87.00 TO STA. 439+00.00	313.00	40	-	1.5	-	-	144.44	-	12.13	6.07	0.05	0.29
STA. 435+87.00 TO STA. 440+62.00	475.00	40	0.75	1.5	-	-	1,391.11	-	-	-	0.53	2.78
STA. 439+00.00 TO STA. 439+35.00	35.00	40	-	1.5	-	-	-	-	177.33	88.67	-	-
STA. 439+35.00 TO STA. 440+62.00	127.00	40	-	1.5	-	-	-	155.56	-	-	0.06	0.31
STA. 440+62.00 TO STA. 441+62.00	100.00	Var fr. 40' to 27'	0.75	1.5	-	-	-	564.44	-	-	0.21	1.13
STA. 441+62.00 TO STA. 462+75.00	2,113.00	26	-	1.5	-	-	-	372.22	31.27	15.63	0.14	0.74
STA. 441+62.00 TO STA. 490+85.00	4,923.00	26	0.75	-	-	-	-	6,104.22	-	-	2.32	12.21
STA. 441+62.00 TO STA. 492+48.09	5,086.09	26	-	1.5	-	-	-	-	1,234.22	-	-	-
STA. 462+75.00 TO STA. 466+40.00	365.00	32	-	1.5	-	-	-	1,297.78	-	-	0.49	2.60
STA. 466+40.00 TO STA. 467+25.00	85.00	29	-	1.5	-	-	-	273.89	-	-	0.10	0.55
STA. 467+25.00 TO STA. 478+80.00	1,155.00	26	-	1.5	-	-	-	3,336.67	-	-	1.27	6.67
STA. 478+80.00 TO STA. 486+67.00	787.00	29	-	1.5	-	-	-	2,535.89	-	-	0.96	5.07
STA. 486+67.00 TO STA. 488+09.00	142.00	26	-	1.5	-	-	-	410.22	-	-	0.16	0.82
STA. 488+09.00 TO STA. 490+38.00	229.00	30	-	1.5	-	-	-	763.33	-	-	0.29	1.53
STA. 490+38.00 TO STA. 490+85.00	47.00	34	-	1.5	-	-	-	177.56	-	-	0.07	0.36
STA. 490+85.00 TO STA. 491+00.00	15.00	34	-	1.5	-	-	-	56.67	-	-	0.02	0.11
STA. 490+85.00 TO STA. 491+00.00	15.00	26	0.75	-	-	-	-	-	-	0.91	-	-
STA. 491+00.00 TO STA. 492+48.09	148.09	34	-	1.5	-	-	-	-	46.99	-	-	-
STA. 492+18.09 TO STA. 492+48.09	30.00	34	-	1.5	113.33	-	-	-	-	-	0.04	0.23
BRIDGE OMISSION (S.N. 068-0027) STA. 492+48.09												
BRIDGE OMISSION (S.N. 068-0027) STA. 492+91.29												
STA. 492+91.29 TO STA. 493+21.29	30.00	34	-	1.5	113.33	-	-	-	-	-	0.04	0.23
STA. 492+91.29 TO STA. 493+91.00	99.71	34	-	1.5	-	-	-	-	31.64	-	-	-
STA. 493+91.00 TO STA. 494+43.00	52.00	32	-	1.5	-	-	-	-	15.53	-	-	-
STA. 494+43.00 TO STA. 499+34.95	491.95	38	-	1.5	-	-	-	-	174.48	-	-	-
STA. 499+04.95 TO STA. 499+34.95	30.00	38	-	1.5	126.67	-	-	-	-	-	0.05	0.25
BRIDGE OMISSION (S.N. 068-0505) STA. 499+34.95												
BRIDGE OMISSION (S.N. 068-0505) STA. 501+51.95												
STA. 501+51.95 TO STA. 501+81.95	30.00	34	-	1.5	113.33	-	-	-	-	-	0.04	0.23
STA. 501+51.95 TO STA. 502+21.00	69.05	34	-	1.5	-	-	-	-	21.91	-	-	-
STA. 502+21.00 TO STA. 503+75.00	154.00	33	-	1.5	-	-	-	-	47.43	-	-	-
STA. 503+75.00 TO STA. 505+50.00	175.00	34	-	1.5	-	-	-	-	55.93	-	-	-
STA. 505+50.00 TO STA. 505+65.00	15.00	26	0.75	-	-	-	-	-	-	0.91	-	-
STA. 505+50.00 TO STA. 505+65.00	15.00	34	-	1.5	-	-	-	56.67	-	-	0.02	0.11
STA. 505+50.00 TO STA. 861+18.00	35,568.00	26	-	1.5	-	-	-	-	8,631.17	-	-	-
STA. 505+65.00 TO STA. 507+83.00	218.00	34	-	1.5	-	-	-	823.56	-	-	0.31	1.65
STA. 505+65.00 TO STA. 860+83.00	35,518.00	26	0.75	-	-	-	-	-	4,309.52	-	-	-
STA. 507+83.00 TO STA. 508+74.00	91.00	30	-	1.5	-	-	-	303.33	-	-	0.12	0.61
STA. 508+74.00 TO STA. 740+20.00	23,146.00	26	-	1.5	-	-	-	66,866.22	-	-	25.41	133.73
STA. 740+20.00 TO STA. 743+70.00	350.00	29	-	1.5	-	-	-	1,127.78	-	-	0.43	2.26
STA. 743+70.00 TO STA. 788+20.00	4,450.00	26	-	1.5	-	-	-	12,855.56	-	-	4.89	25.71
STA. 788+20.00 TO STA. 789+30.00	110.00	Var fr. 29' to 32'	-	1.5	-	-	-	186.39	-	-	0.07	0.37
STA. 789+30.00 TO STA. 789+65.00	35.00	Var fr. 32' to 33'	-	1.5	-	-	-	63.19	-	-	0.02	0.13
STA. 789+65.00 TO STA. 791+00.00	135.00	33	-	1.5	-	-	495.00	-	-	-	0.19	0.99
STA. 791+00.00 TO STA. 796+50.00	550.00	40	-	1.5	-	-	2,444.44	-	-	-	0.93	4.89
STA. 796+50.00 TO STA. 797+00.00	50.00	41	-	1.5	-	-	227.78	-	-	-	0.09	0.46
STA. 797+00.00 TO STA. 805+00.00	800.00	42	-	1.5	-	-	3,733.33	-	-	-	1.42	7.47
STA. 805+00.00 TO STA. 806+98.00	198.00	34	-	1.5	-	-	748.00	-	-	-	0.28	1.50
STA. 806+98.00 TO STA. 807+97.00	99.00	15.5	-	1.5	-	-	170.50	-	-	-	0.06	0.34
STA. 807+97.00 TO STA. 808+32.00	35.00	26	-	1.5	-	-	-	101.11	-	-	0.04	0.20
STA. 808+32.00 TO STA. 848+83.00	4,051.00	26	-	1.5	-	-	-	11,702.89	-	-	4.45	23.41
STA. 848+83.00 TO STA. 849+18.00	35.00	26	-	1.5	-	-	-	101.11	-	-	0.04	0.20
STA. 849+18.00 TO STA. 849+50.00	32.00	29	-	1.5	-	-	103.11	-	-	-	0.04	0.21
STA. 849+50.00 TO STA. 854+75.00	525.00	32	-	1.5	-	-	1,866.67	-	-	-	0.71	3.73
STA. 854+75.00 TO STA. 855+10.00	35.00	32	-	1.5	-	-	-	124.44	-	-	0.05	0.25
STA. 855+10.00 TO STA. 859+40.70	430.70	32	-	1.5	-	-	-	1,531.38	-	-	0.58	3.06
STA. 859+40.70 TO STA. 860+98.00	157.30	26	-	1.5	-	-	-	454.42	-	-	0.17	0.91
STA. 860+83.00 TO STA. 860+98.00	15.00	26	0.75 to 0	-	-	-	-	-	-	0.91	-	-
STA. 860+98.00 TO STA. 861+18.00	20.00	26	-	1.5	57.78	-	-	-	-	-	0.02	0.12
Mulberry Grove Rd.												
STA. 8+73.00 TO STA. 8+63.00	10.00	26	-	1.5	28.89	-	-	-	-	-	0.01	0.06
STA. 9+87.00 TO STA. 8+73.00	Area: 7,783.26 Sq. Ft.	-	-	1.5	-	864.81	-	-	72.64	-	0.33	1.73
INCIDENTAL HMA SURF (HMA ENTR. & SIDE ROADS) INCLUDED IN HMA SURF REM BUTT JT.												
					7,049	865	12,823	121,925	11,488	5,485	61	286

FILE NAME =  
c:\pwwork\pwwid\COXJ\wms22861\ShhSchedul...  
PLOT SCALE = 100.0000' / IN.  
PLOT DATE = Aug-13-2009 10:29:26AM

USER NAME = coxjw  
DESIGNED - JWC  
DRAWN - JWC  
CHECKED - RSC  
DATE - 7/14/09

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 7 OF 7 SHEETS STA. TO STA.

F.A.P. RTE. 777  
SECTION 10RS-5  
COUNTY Montgomery  
TOTAL SHEETS 54  
SHEET NO. 19  
CONTRACT NO. 72A68  
ILLINOIS FED. AID PROJECT