

DESCRIPTION	STATION	fr. E. O. P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		HMA. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr. AREA (SQ FT)
					AREA	TOTAL	AREA	TOTAL	AREA	TOTAL		
					(SQ FT)	(TON)	(SQ FT)	(TON)	(SQ FT)	(TON)		
LIMITS OF IMPROVEMENT:		STA. 399+56.50										
SECTION BEGINS		STA. XXX+XX.XX										
HMA, P. E. (South St.)	STA 400+20.00 LT	7	30	2.25 to 1.5			259.00	3.02			3.02	183.00
HMA, P. E. (Reeves Ct.)	STA 400+31.86 RT	9	36	2.25 to 1.5					405.00	4.73	4.73	153.00
HMA, P. E. Alley	STA 400+20.00 LT	7	30	2.25 to 1.5			259.00	3.02			3.02	183.00
HMA, P. E. Alley	STA 401+69.70 LT	9	28	2.25 to 1.5					333.00	3.89	3.89	129.00
HMA, P. E.	STA 402+48.25 RT	9	28	2.25 to 1.5					333.00	3.89	3.89	129.00
HMA, P. E.	STA 402+81.00 LT	10	20	2.25 to 1.5			300.00	3.50			3.50	93.00
HMA, P. E. (N. Ash St.)	STA 403+02.00 LT	10	21	2.25 to 1.5			310.00	3.62			3.62	96.00
HMA, P. E. (S. Ash St.)	STA 404+41.70 LT	9	23	2.25 to 1.5					288.00	3.36	3.36	114.00
HMA, P. E.	STA 404+57.17 RT	9	31	2.25 to 1.5					360.00	4.20	4.20	138.00
HMA, P. E.	STA 406+23.00 LT	11	20	2.25 to 1.5			341.00	3.98			3.98	105.00
HMA, P. E. Alley	STA 407+26.00 LT	7	31	2.25 to 1.5			266.00	3.10			3.10	138.00
HMA, P. E. (Walnut St.)	STA 407+82.05 RT	9	27	2.25 to 1.5					324.00	3.78	3.78	126.00
HMA, P. E. w/MBT	STA 409+72.10 RT	9	36	2.25 to 1.5					405.00	4.73	4.73	153.00
HMA, P. E. w/MBT	STA 412+57.00 LT	15	14	2.25 to 1.5			435.00	5.08			5.08	87.00
HMA, P. E.	STA 412+78.00 RT	7	35	2.25 to 1.5			294.00	3.43			3.43	138.00
HMA, P. E.	STA 413+91.00 RT	7	31	2.25 to 1.5			266.00	3.10			3.10	260.79
HMA, P. E.	STA 415+40.00 LT	7	29	2.25 to 1.5			252.00	2.94			2.94	132.00
HMA, P. E.	STA 415+67.00 RT	7	31	2.25 to 1.5			266.00	3.10			3.10	260.79
HMA, P. E.	STA 417+13.00 RT	7	32	2.25 to 1.5			273.00	3.19			3.19	263.79
HMA, P. E.	STA 417+24.00 LT	7	31	2.25 to 1.5			266.00	3.10			3.10	260.79
HMA, P. E.	STA 417+93.00 RT	7	31	2.25 to 1.5			266.00	3.10			3.10	260.79
HMA, P. E.	STA 419+37.00 RT	7	35	2.25 to 1.5			294.00	3.43			3.43	272.79
HMA, P. E.	STA 420+44.00 RT	7	33	2.25 to 1.5			280.00	3.27			3.27	266.79
HMA, P. E.	STA 421+86.00 RT	7	33	2.25 to 1.5			280.00	3.27			3.27	266.79
HMA, P. E.	STA 422+60.00 RT	7	34	2.25 to 1.5			287.00	3.35			3.35	269.79
HMA, P. E.	STA 423+12.00 RT	7	41	2.25 to 1.5			336.00	3.92			3.92	290.79
HMA, P. E.	STA 424+01.00 RT	7	31	2.25 to 1.5			266.00	3.10			3.10	260.79
HMA, P. E.	STA 424+73.00 RT	7	32	2.25 to 1.5			273.00	3.19			3.19	263.79
HMA, P. E.	STA 425+59.00 RT	7	33	2.25 to 1.5			280.00	3.27			3.27	266.79
HMA, P. E.	STA 426+96.00 RT	7	32	2.25 to 1.5			273.00	3.19			3.19	263.79
HMA, P. E.	STA 427+43.00 RT	7	30	2.25 to 1.5			259.00	3.02			3.02	257.79
HMA, P. E. w/MBT	STA 427+70.00 LT	15	16	2.25 to 1.5			465.00	5.43			5.43	93.00
HMA, P. E.	STA 428+46.00 LT	7	30	2.25 to 1.5			259.00	3.02			3.02	135.00
HMA, P. E.	STA 429+63.00 RT	7	21	2.25 to 1.5			196.00	2.29			2.29	108.00
HMA, P. E.	STA 435+53.00 RT	7	29	2.25 to 1.5			252.00	2.94			2.94	254.79
TR 549 (Happy Ln.)	STA 442+76.00 LT	9	28	2.25 to 1.5					333.00	3.89	3.89	129.00
HMA, C. E. (Olive Hill Cemetery)	STA 443+64.00 RT	9	25	2.25 to 1.5			306.00	3.57			3.57	120.00
HMA, P. E. w/MBT	STA 443+68.00 LT	15	19	2.25 to 1.5			510.00	5.95			5.95	102.00
HMA, C. E. (Rocky Ford Park)	STA 444+36.00 RT	9	30	2.25 to 1.5			351.00	4.10			4.10	135.00
HMA, P. E. w/MBT	STA 445+27.00 LT	15	15	2.25 to 1.5			450.00	5.25			5.25	90.00
HMA, P. E. w/MBT	STA 446+86.00 LT	15	18	2.25 to 1.5			495.00	5.78			5.78	99.00
HMA, P. E. w/MBT	STA 448+08.00 LT	15	12	2.25 to 1.5			405.00	4.73			4.73	81.00
HMA, M. B. T. (No Entr.)	STA 450+00.00 LT	7	20	2.25 to 1.5			189.00	2.21			2.21	183.00
HMA, P. E.	STA 450+00.00 RT	7	33	2.25 to 1.5			280.00	3.27			3.27	266.79
HMA, P. E.	STA 454+31.00 RT	7	28	2.25 to 1.5			245.00	2.86			2.86	251.79
HMA, M. B. T. (No Entr.)	STA 453+60.00 LT	7	20	2.25 to 1.5			189.00	2.21			2.21	183.00
HMA, P. E.	STA 456+00.00 RT	7	21	2.25 to 1.5			196.00	2.29			2.29	230.79
HMA, M. B. T. (No Entr.)	STA 456+16.00 LT	7	20	2.25 to 1.5			189.00	2.21			2.21	183.00
HMA, P. E. w/MBT	STA 458+75.00 LT	15	31	2.25 to 1.5			690.00	8.05			8.05	138.00
HMA, P. E. w/MBT	STA 459+55.00 LT	15	23	2.25 to 1.5			570.00	6.65			6.65	114.00
HMA, P. E. w/MBT	STA 460+56.00 LT	15	14	2.25 to 1.5			435.00	5.08			5.08	87.00
HMA, P. E.	STA 460+58.00 RT	7	27	2.25 to 1.5			238.00	2.78			2.78	126.00
HMA, P. E.	STA 462+58.00 RT	7	32	2.25 to 1.5			273.00	3.19			3.19	141.00
HMA, P. E.	STA 464+32.00 RT	4	33	2.25 to 1.5			148.00	1.73			1.73	144.00
HMA, M. B. T. (No Entr.)	STA 464+60.00 LT	4	20	2.25 to 1.5			96.00	1.12			1.12	183.00
HMA, P. E.	STA 466+89.00 RT	7	19	2.25 to 1.5			182.00	2.12			2.12	102.00
HMA, P. E. w/MBT	STA 467+63.00 LT	15	27	2.25 to 1.5			630.00	7.35			7.35	126.00
HMA, P. E. w/MBT	STA 471+98.00 LT	15	13	2.25 to 1.5			420.00	4.90			4.90	84.00
HMA, P. E.	STA 472+74.00 RT	7	22	2.25 to 1.5			203.00	2.37			2.37	111.00
HMA, P. E.	STA 473+64.00 RT	7	25	2.25 to 1.5			224.00	2.61			2.61	120.00
PROJECT SUB-TOTAL							15,967.00	186.28	2,781.00	32.45	218.73	10,205.01

FILE NAME =  
 c:\pwwork\pwwid07\COXJW\dms22861\Sh01.dgn

USER NAME = coxjw  
 PLOT SCALE = 1/8" = 100'-0"  
 PLOT DATE = Aug-13-2009 10:36:05AM

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE - 7/1/09

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

DETAILS FOR RURAL ENTRANCE,  
 MAILBOX TURNOUT & SIDE ROAD  
 SCALE: SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.  
 777 IORS-5 Montgomery 54 52  
 CONTRACT NO. 72A68  
 ILLINOIS FED. AID PROJECT