

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

80% FED.
20% STATE

ROUTE SBI 16A (CRESS CIRCLE)				CONSTRUCTION TYPE CODE	
SUMMARY OF QUANTITIES				RWY	STR
CODE NO.	ITEM	UNIT	TOTAL	1000-2A	X028-2A
20200100	EARTH EXCAVATION	CU. YD.	145	145	
20300100	CHANNEL EXCAVATION	CU. YD.	13	13	
20400800	FURNISHED EXCAVATION	CU. YD.	250	250	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5	
25100630	EROSION CONTROL BLANKET	SQ. YD.	888	888	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	378	378	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ. YD.	166	166	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ. YD.	128	128	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
40600300	AGGREGATE (PRIME COAT)	TON	0.5	0.5	

80% FED.
20% STATE

ROUTE SBI 16A (CRESS CIRCLE)				CONSTRUCTION TYPE CODE	
SUMMARY OF QUANTITIES				RWY	STR
CODE NO.	ITEM	UNIT	TOTAL	1000-2A	X028-2A
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	8	8	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	54	54	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	11	11	
44000100	PAVEMENT REMOVAL	SQ. YD.	122	122	
44000400	GUTTER REMOVAL	FOOT	175	175	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	25	25	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU. YD.	7.0	7.0	
54001000	BOX CULVERT END SECTIONS	EACH	2		2
54010608	PRECAST CONCRETE BOX CULVERT 6' X 8'	FOOT	39.0		39.0
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POST	FOOT	100	100	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50	50	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	133	133	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2	
67100100	MOBILIZATION	L. SUM	1	1	

* Specialty Items

FILE NAME =	USER NAME = laughlinr1	DESIGNED - DPS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ROUTE SBI 16A (CRESS CIRCLE)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72873-sht-summary.dgn	DRAWN - DPS	REVISED -	(21FR#1)ACB			MONTGOMERY	20	3		
PLOT SCALE = 28.0000' / IN.	CHECKED - FML	REVISED -	CONTRACT NO. 72873							
PLOT DATE = Jul-24-2009 10:35:36AM	DATE - 01/2009	REVISED -	SCALE: N/A			SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT