

Urethane Pavement Marking - Line 5"

Location	Sta.	Sta.	Pass (ft)	DBL NP (ft)	NBNP (ft)	SBNP (ft)
	492+61	487+06				555
	487+06	477+81		925		
Omission	477+81	466+90				Buckhorn / Estill turn lanes - Omission
	466+90	459+39		751		
	461+07	444+89			1618	
	444+89	443+32		157		
	443+32	433+55				977
	433+55	364+88	6867			
Sta Eq (Ah)	364+88					
Sta Eq (Bk)	364+95					
	364+95	363+31	164			
	363+31	355+18			813	
	355+18	344+59		1059		
	344+59	333+82				1077
	333+82	328+82		500		
Andrew Rd - Thermo	328+82	315+30				Thermo - see schedule
	315+30	310+30				500
	310+30	296+49	1381			
	296+49	286+04		1045		
	286+04	280+20				584
	280+20	265+96	1424			
	265+96	258+68			728	
	258+68	241+19		1749		
	241+19	233+04	815			
	233+04	222+96			1008	
	222+96	199+48		2348		
Sta. Eq (AH)	199+48					
Sta. Eq (BK)	202+89					
	202+89	193+66		923		
Sta. Eq (AH)	193+66					
Sta. Eq (BK)	115+24					
	115+24	80+00		3524		
	80+00	33+03	4697			
Sta Reverses	33+03					
Sta Reverses	+44					
	+44	17+92	1748			
	17+92	22+92			500	

Note: Add extra 2x quantity for edge lines	x2.25	x4	x3.25	x3.25
	38466	51924	15168	12002

Total = 117,560
 -2960
Final = 114,600

Note: No EOP markings between 492+61 to 477+81 (deduct 2960')

White = 73,914
 Yellow = 40,686

Center Line Rumble Strips

Location	Sta	to	Sta	8" Length (ft)	20" Length (ft)
	492+61		477+81		1480
Buckhorn/Estill Omission	477+81		466+90		
	466+90		433+55		3335
	433+55		364+88	6867	
Sta Eq (Ah)	364+88				
Sta Eq (Bk)	364+95				
	364+95	363+31		164	
	363+31	328+82			3449
Andrew Rd Omission	328+82		315+30		
	315+30		310+30		500
	310+30		296+49	1381	
	296+49		280+20		1629
	280+20		265+96	1424	
	265+96		241+19		2477
	241+19		233+04	815	
	233+04		199+48		3356
Sta Eq (Ah)	199+48				
Sta Eq (Bk)	202+89				
	202+89		193+66		923
Sta Eq (Ah)	193+66				
Sta Eq (Bk)	115+24				
	115+24		108+18		706
Cantrall Omission	108+18		77+92		
	77+92		33+03	4489	
Sta Reverses	33+03				
Sta Reverses	+44				
	+44		17+92	1748	
	17+92		22+92		500
				1	18355

* D6 RUMBLESTRIP, MRKING 2010