

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				80% FED/20% STATE	
CODE NO.	ITEM			ROADWAY 1000-2A	BRIDGE X001-2A
20200100	EARTH EXCAVATION	CU YD	980	980	
20400800	FURNISHED EXCAVATION	CU YD	3445	3445	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	116		116
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.90	0.90	
25100630	EROSION CONTROL BLANKET	SQ YD	4119	4119	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	270	270	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	1677	1677	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2219	1060	1159
28200200	FILTER FABRIC	SQ YD	2219	1060	1159
35650700	BASE COURSE WIDENING	SQ YD	512	512	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	274	274	
40600300	AGGREGATE (PRIME COAT)	TON	4	4	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	149	149	
40600990	TEMPORARY RAMP	SQ YD	412	412	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	740	740	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	264	264	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	222	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44	
44000100	PAVEMENT REMOVAL	SQ YD	237	237	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	813	813	
44000400	GUTTER REMOVAL	FOOT	917	917	
44002600	GUTTER OUTLET REMOVAL	FOOT	150	150	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	85	85	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	32	32	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	47	47	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	133	133	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	85	85	
50200100	STRUCTURE EXCAVATION	CU YD	169		169
50300225	CONCRETE STRUCTURES	CU YD	115		115.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	258.6		258.6

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				80% FED/20% STATE	
CODE NO.	ITEM			ROADWAY 1000-2A	BRIDGE X001-2A
50300260	BRIDGE DECK GROOVING	SQ YD	837		837
50300280	CONCRETE ENCASEMENT	CU YD	8.6		8.6
50300300	PROTECTIVE COAT	SQ YD	839		839
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	1136		1136
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	68140		68140
50800515	BAR SPLICERS	EACH	675		675
51201610	FURNISHING STEEL PILES HP12X63	FOOT	360		360
51201900	FURNISHING STEEL PILES HP14X89	FOOT	308		308
51202305	DRIVING PILES	FOOT	220		220
51203610	TEST PILE STEEL HP12X63	EACH	1		1
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84		84
60100905	PIPE DRAINS 4"	FOOT	283	283	
60109580	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	154		154
60500060	REMOVING INLETS	EACH	4	4	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	13.7	13.7	
60602800	CONCRETE CUTTER, TYPE B	FOOT	605.0	605.0	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	350	350	
* 63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	1	1	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	328	328	
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	176	176	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	11	11	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
35650450	BASE COURSE WIDENING REMOVAL	SQ YD	101	101	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	

* SPECIALTY ITEMS