

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				80% FED/20% STATE	
CODE NO.	ITEM			ROADWAY <i>I000-2A</i>	BRIDGE <i>X081-2A</i>
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	480	480	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	3571	3571	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	40	40	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	625	625	
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	3571	3571	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13	13	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	470	470	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	218		218
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1	EACH	1		1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	88		88
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	2	2	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0073100	TEMPORARY SHORING	EACH	1		1
* <i>X0326301</i>	SETTING AND DRIVING PILES IN ROCK <i>TEST</i>	EACH	12		12
* <i>X0326317</i>	SETTING AND DRIVING PILES IN ROCK, HP12X63 <i>TEST</i>	EACH	1		1
* <i>X0326318</i>	SETTING AND DRIVING PILES IN ROCK, HP14X89 <i>TEST</i>	EACH	1		1

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED - WLL 10/06/08	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 128 OVER WOLF CREEK SCHEDULE OF QUANTITIES</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	Rev.	
#FILE#		DRAWN - RJA 10/07/08	REVISED -			2801	(102B)B-1	EFFINGHAM	51	4		
PLOT SCALE = #SCALE#		CHECKED - GBM 10/14/08	REVISED -			CONTRACT NO. 74232						
PLOT DATE = #DATE#		DATE - 10/15/08	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.