

FURNISHING AND INSTALLING PROPERTY MARKERS		
LOCATION & DESCRIPTION		Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS
LOCATION	DESCRIPTION	EACH
STA. 970+05.00, 0.13' RT	IRON PIN - NW CORNER, SECTION 7 MONUMENT RECORD - VOL. 2439, PAGE 245	1
STA. 972+67.09, 0.24' RT	IRON PIN - SE CORNER, SECTION 1 MONUMENT RECORD - BOOK 1, PAGE 301	1
TOTAL		2

PAINT PAVEMENT MARKING - LINE 4"		
LOCATION		78001110 PAINT PAVEMENT MARKING - LINE 4"
		FOOT
LT EDGE	STA. 968+50.00 TO STA. 980+50.00	1200
RT EDGE	STA. 968+50.00 TO STA. 980+50.00	1200
CENTERLINE	STA. 968+50.00 TO STA. 971+80.00 SKIP-DASH	83
CENTERLINE	STA. 971+80.00 TO STA. 980+50.00 SOLID-DASH	1088
TOTAL		3571

PAVEMENT MARKING REMOVAL					
LOCATION					78300100 PAVEMENT MARKING REMOVAL
STAGE	LOCATION		WIDTH	LENGTH	SQ FT
STAGE I	STA. 970+67.00 TO STA. 977+88.00, RT	SOLID	4"	721	240.3
STAGE I	STA. 969+24.50 TO STA. 970+93.50, CL	SKIP-DASH	4"	42.25	14.1
STAGE I	STA. 977+58.50 TO STA. 979+18.50, CL	SOLID-DASH	4"	200	66.7
STAGE II	STA. 970+71.00 TO STA. 973+44.50, LT	SOLID	4"	273.5	91.2
STAGE II	STA. 976+07.50 TO STA. 977+81.00, LT	SOLID	4"	173.5	57.8
TOTAL					470.1

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	
LOCATION	78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
EACH	
STA. 973+80.50 TO STA. 975+71.50 (PAVEMENT MARKERS ON 80' cts.)	2
TOTAL	2

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	78100100 RAISED REFLECTIVE PAVEMENT MARKER
EACH	
STA. 968+50.00 TO STA. 973+80.50 (PAVEMENT MARKERS ON 80' cts.)	7
STA. 975+71.50 TO STA. 980+50.00 (PAVEMENT MARKERS ON 80' cts.)	6
TOTAL	13

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
EACH	
STA. 971+01.21, 2.7' LT	1
STA. 977+50.79, 2.7' LT	1
TOTAL	2

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
LOCATION	66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
EACH	
STA. 970+05.08, 60.0' LT	1
STA. 970+10.43, 60.0' RT	1
STA. 971+50.00, 70.0' RT	1
STA. 972+00.00, 115.0' LT	1
STA. 972+70.16, 70.0' RT	1
STA. 972+80.24, 70.0' RT	1
STA. 972+80.26, 115.0' LT	1
STA. 973+50.00, 70.0' LT	1
STA. 974+70.00, 60.0' RT	1
STA. 974+92.58, 115.0' LT	1
STA. 975+01.52, 115.0' LT	1
TOTAL	11

GUARDRAIL MARKERS, TYPE A	
LOCATION	78200410 GUARDRAIL MARKERS, TYPE A
EACH	
STA. 971+24.86 TO STA. 973+81.11, RT	4
STA. 972+24.85 TO STA. 973+81.11, LT	4
STA. 975+70.90 TO STA. 977+02.15, LT	4
STA. 975+70.90 TO STA. 977+27.15, RT	4
TOTAL	16

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
EACH	
STA. 971+13.66, 2.4' RT	1
STA. 977+38.33, 2.4' RT	1
TOTAL	2

TERMINAL MARKER - DIRECT APPLIED	
LOCATION	78201000 TERMINAL MARKER - DIRECT APPLIED
EACH	
STA. 971+24.86, RT	1
STA. 972+24.85, LT	1
STA. 977+27.15, RT	1
TOTAL	3