

ITEM NUMBER	PAY ITEM	UNIT	URBAN	
			80%/20%	
			FED/ST.	QUANTITY X171-2A
20200100	EARTH EXCAVATION	CU YD	4,576	
20800150	TRENCH BACKFILL	CU YD	85	
25000210	SEEDING, CLASS 2A	ACRE	0.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	80	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	80	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	80	
25100115	MULCH, METHOD 2	ACRE	0.8	
25100630	EROSION CONTROL BLANKET	SQ YD	2,930	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	220	
28000300	TEMPORARY DITCH CHECKS	EACH	25	
28000400	PERIMETER EROSION BARRIER	FOOT	1,949	
28000500	INLET AND PIPE PROTECTION	EACH	5	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	699	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	6,125	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.1	
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	8,251	
42001300	PROTECTIVE COAT	SQ YD	3,233	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	659	
42100325	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11 1/4"	SQ YD	2,458	
42100925	PAVEMENT REINFORCEMENT 11 1/4"	SQ YD	2,458	
44000100	PAVEMENT REMOVAL	SQ YD	2,869	
44004000	PAVED DITCH REMOVAL	FOOT	221	
44004250	PAVED SHOULDER REMOVAL	SQ YD	6,217	
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	1,860	
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1	
50101800	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 2	EACH	1	
50102400	CONCRETE REMOVAL	CU YD	246.3	
50157300	PROTECTIVE SHIELD	SQ YD	1,908	
50200100	STRUCTURE EXCAVATION	CU YD	333	
50300225	CONCRETE STRUCTURES	CU YD	372.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,552.5	
50300260	BRIDGE DECK GROOVING	SQ YD	4,905	
50300300	PROTECTIVE COAT	SQ YD	6,052	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	
50500505	STUD SHEAR CONNECTORS	EACH	13,026	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	436,480	
50800515	BAR SPLICERS	EACH	3,150	
51500100	NAME PLATES	EACH	2	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	252	
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	242	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	17	
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	17	
52100520	ANCHOR BOLTS, 1"	EACH	84	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	34	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	34	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	785	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	302	
Δ 55037900	STORM SEWERS TO BE CLEANED 15"	FOOT	138	
58700300	CONCRETE SEALER	SQ FT	7,138	
59000200	EPOXY CRACK INJECTION	FOOT	290	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	23	
60107700	PIPE UNDERDRAINS 6"	FOOT	6,157	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	319	
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	
60246705	MEDIAN INLET (604101), SPECIAL	EACH	3	
60500090	REMOVING INLETS TO MAINTAIN FLOW	FOOT	1	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' POSTS	FOOT	4,322.5	
* 63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	225	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	9	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	
63200310	GUARDRAIL REMOVAL	FOOT	4,730	
63500105	DELINEATORS	EACH	3	
63500120	DELINEATOR REMOVAL	EACH	3	

Δ NON-PARTICIPATING 100% STATE

ITEM NUMBER	PAY ITEM	UNIT	URBAN	
			80%/20%	
			FED/ST.	QUANTITY X171-2A
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	8	
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	115	
63700805	CONCRETE BARRIER TRANSITION	FOOT	5	
63800048	GLARE SCREEN BLADES 48"	EACH	800	
64200105	SHOULDER RUMBLE STRIP	FOOT	6,566	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	36	
67100100	MOBILIZATION	L SUM	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	832	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	96	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	78,757	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	14,695	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	26,435	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5,414	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	9,281	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23,080	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	728	
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	3,750	
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	147	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	28	
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	2,556	
* 78100300	REPLACEMENT REFLECTOR	EACH	505	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	78	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	44	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	36	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	9,400	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2,556	
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	8,695	
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1,760	
* X8440116	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	3	
* 09502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	150	
* X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	505	
X0323644	PAVEMENT MARKING GROOVING	FOOT	3,897	
X0323830	DRAINAGE SCUPPERS, DS-II	EACH	8	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	567	
X0324952	DETOUR SIGNING	L SUM	1	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	27	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	271.4	
X0325502	MEDIAN BARRIER GATE SYSTEM	EACH	1	
* X0325513	PIPE UNDERDRAIN REMOVAL, SPECIAL	FOOT	6,334	
* X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	105	
* X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	1	
X0325648	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 650K	EACH	17	
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	
X0325759	TRAFFIC CONTROL AND PROTECTION - STAGE 1	L SUM	1	
X0325760	TRAFFIC CONTROL AND PROTECTION - STAGE 2	L SUM	1	
X0325761	TRAFFIC CONTROL AND PROTECTION - STAGE 3	L SUM	1	
* X8950060	REMOVE EXISTING CONTROLLER	EACH	1	
Z0018800	DRAINAGE SYSTEM	L SUM	1	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	
* X0326686	PORTLAND CEMENT CONCRETE BASE COURSE 4"	SQ YD	2,452	
* X0326677	HIGH TENSION CABLE MEDIAN BARRIER REMOVAL	FOOT	592	
* X0326687	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL REMOVE	EACH	3	
B1300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2	

* SPECIALTY ITEM

FILE NAME = P:\0606018\dgn\CADD Sheets\0876876-shd-000-001.dgn	USER NAME = jheger	DESIGNED - DRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 64	SECTION 82-2VB-2	COUNTY ST. CLAIR	TOTAL SHEETS 153	SHEET NO. 3		
PLOT SCALE = 8.0691' / IN.	PLOT DATE = 8/7/2009	DRAWN - MLS	REVISED -			SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 8 [ILLINOIS] FED. AID PROJECT		
		CHECKED - SJK	REVISED -			CONTRACT NO. 76867						
		DATE -	REVISED -			Rev.						