

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			<i>URBAN</i> 100% STATE CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			<i>URBAN</i> 100% STATE CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	-----	-----	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19									
40600300	AGGREGATE (PRIME COAT)	TON	97	97			*88600600	DETECTOR LOOP REPLACEMENT	FOOT	5483	5483		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2595	2595									
40600990	TEMPORARY RAMP	SO YD	3613	3613									
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	5190	5190									
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	68591	68591									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	140	140									
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SO YD	70	70									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2000	2000									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	871	871									
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	140	140									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5									
67100100	MOBILIZATION	L SUM	1	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1									
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	31920	31920									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	419	419									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45600	45600									
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2241	2241									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	641	641									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	289	289									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	11379	11379									
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	419	419									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45600	45600									
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2241	2241									
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	641	641									
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	289	289									
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	529	529									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	529	529									

\*Specialty Items

*Rev.*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN -	REVISED -			600	60-(30,31,128)-2	MADISON	42	3
		CHECKED -	REVISED -			CONTRACT NO. 76B87		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		
		PLT DATE = #DATE#	DATE -			SCALE: -----	SHEET NO. 1 OF 1 SHEETS	STA. -----	TO STA. -----	