

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE FUNDED			
			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY J000	TRAFFIC SIGNS Y002-1C	HIGHWAY LIGHTING Y030-1E
* 72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	20		20	
* 72900100	METAL POST - TYPE A	FOOT	89		89	
* 72900200	METAL POST - TYPE B	FOOT	293		293	
* 73000100	WOOD SIGN SUPPORT	FOOT	270		270	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	184	184		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,849	4,849		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	461	461		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	157	157		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,990	1,990		
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	655	655		
* 78004100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LETTERS AND SYMBOLS	SQ FT	48	48		
* 78004150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LINE 12"	FOOT	184	184		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,188	1,188		
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	184	184		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	131	131		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	61	61		
* 78200300	PRISMATIC CURB REFLECTOR	EACH	45	45		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	122	122		
* 81100220	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., PVC COATED GALVANIZED STEEL	FOOT	380		380	
* 81300210	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 4" X 4"	EACH	8		8	
* 81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	4		4	
* 81603035	UNIT DUCT, 600V, 2-1/C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	390		390	
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	500		500	
* 81800230	AERIAL CABLE, 2-1/C NO. 6 WITH MESSENGER WIRE	FOOT	270		270	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	370		370	
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2		2	
* 82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8		8	
* 83057290	LIGHT POLE, WOOD, 50 FOOT, CLASS 4	EACH	1		1	
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	13		13	
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2		2	
84200700	LIGHTING FOUNDATION REMOVAL	EACH	4		4	
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1
89502380	REMOVE EXISTING HANDHOLE	EACH	4			4

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE FUNDED			
			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY J000	TRAFFIC SIGNS Y002-1C	HIGHWAY LIGHTING Y030-1E
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5			5
* A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3		
* B2001124	TREE, CERCIUS CANADENSIS (EASTERN REDBUD) 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4		
* B2002220	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORN), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12	12		
Z0002750	BARRICADES, TYPE III	EACH	3	3		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
* X0322787	CLEANING EXISTING SANITARY SEWERS	FOOT	1,877	1,877		
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4			4
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	189	189		
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	626	626		
* X0326688	SIGN FACE SPECIAL	SQ FT	28		28	
X0326689	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) (COLORED)	SQ YD	290	290		
* A3005214	TREE, ZELKOVA SERRATA (JAPANESE ZELKOVA), 3" CALIPER, BALLED AND BURLAPPED	EACH	11	11		
* C2C09918	SHRUB, SPIREA X BUNALDA GOLDFLAME (GOLDFLAME SPIREA), 18" HEIGHT, CONTAINER	EACH	10	10		
* K1004467	PERENNIAL PLANTS, ORNAMENTAL (SUMALD) HERBACEOUS TYPE	UNIT	12	12		
* K1004465	PERENNIAL PLANTS, BULBS	UNIT	8	8		
* X0326690	TOPSOIL PLANTING MIX, 12"	SQ YD	213	213		

* DENOTES SPECIALTY ITEM

6/13/2009 10:34:14 AM

FILE NAME = DBTRI-76C38-sht-summary01-02.dgn	USER NAME = jdf	DESIGNED - LDC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
MODEL NAME = DBTRI-76C38-sht-summary-02	DRAWN -	REVISED -				*	82-1-10N	ST. CLAIR	68	6	
PLOT SCALE = 1:1	CHECKED - GEB	REVISED -				* 9166/9180					
PLOT DATE = 8/13/2009	DATE - 08/14/09	REVISED -				CONTRACT NO. 76C38					
SCALE: NONE					SHEET NO. 2 OF 2 SHEETS		STA. ----- TO STA. -----		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		