

SIGN AND POST SCHEDULE

STATION	OFFSET	TYPE	DESCRIPTION	SIGN PANEL T1 (SQ FT)	SIGN PANEL T1 SPL (SQ FT)	SIGN PANEL T3 SPL (SQ FT)	SIGN FACE SPECIAL (SQ FT)	METAL POST TY A (SQ FT)	METAL POST TY B (SQ FT)	WOOD SIN SUPPORT (SQ FT)	COMMENT
18TH STREET											
199+58	RT	R1-1	STOP	6.3						15	
199+58	RT	R3-2	LEFT TURN PROHIBITION	4.0							MOUNT WITH R1-1
199+72	LT	R3-1	RIGHT TURN PROHIBITION	4.0				12			
200+64	LT	R1-1	STOP	6.3					13		
201+03	RT	W2-6	CIRCULAR INTERSECTION	6.3						16	
201+03	RT	W13-1	ADVISORY SPEED (20 MPH)	2.3							MOUNT WITH W2-6
201+34	RT	W12-2P	LOW CLEARANCE (14 FT 2 IN)				14.0				MOUNT ON BRIDGE BEAM
202+03	RT	W3-2a	YIELD AHEAD	9.0						15	
202+17	RT	R4-7	KEEP RIGHT	5.0				13			
202+76	RT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
202+76	RT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
202+82	LT	W12-2P	LOW CLEARANCE (14 FT 0 IN)				14.0				MOUNT ON BRIDGE BEAM
202+91	LT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
202+91	LT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
203+03	RT	R1-2	YIELD	3.9					13		
203+03	RT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
203+08	LT	DGS-1	DESTINATION GUIDE SIGN 1		6.0				24		MOUNT ON TWO TYPE B POSTS
203+08	RT	R1-2	YIELD	3.9					13		
203+08	RT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
203+55	RT	R6-1R	ONE WAY	3.0					26		MOUNT ON TWO TYPE B POSTS
203+55	RT	W1-8R	CHEVRON ALIGNMENT (4 EACH)	6.0							
203+70	RT	R6-1R	ONE WAY	3.0					26		MOUNT ON TWO TYPE B POSTS
203+70	RT	W1-8R	CHEVRON ALIGNMENT (4 EACH)	6.0							
203+76	LT	R6-1R	ONE WAY	3.0					26		MOUNT ON TWO TYPE B POSTS
203+76	LT	W1-8R	CHEVRON ALIGNMENT (4 EACH)	6.0							
204+20	RT	R5-2a	NO TRUCKS	4.0				12			
204+25	LT	DGS-1	DESTINATION GUIDE SIGN 1		6.0				24		MOUNT ON TWO TYPE B POSTS
204+26	LT	R1-2	YIELD	3.9					13		
204+26	LT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
204+27	LT	R1-2	YIELD	3.9					13		
204+27	LT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
204+60	RT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
204+60	RT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
204+76	LT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
204+76	LT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
204+77	LT	R4-7	KEEP RIGHT	5.0				13			
205+27	LT	W3-2a	YIELD AHEAD	9.0						15	
206+27	LT	W2-6	CIRCULAR INTERSECTION	6.3						16	
206+27	LT	W13-1	ADVISORY SPEED (20 MPH)	2.3							MOUNT WITH W2-6
207+27	LT	W12-2	LOW CLEARANCE (14 FT 0 IN)	9.0						15	
BAUGH AVENUE											
14+64	LT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
14+64	LT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
14+94	RT	DGS-2	DESTINATION GUIDE SIGN 2		7.5				24		MOUNT ON TWO TYPE B POSTS
RAMP D											
400+30	LT	R1-2	YIELD	3.9					13		
400+30	LT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
400+33	RT	R1-2	YIELD	3.9					13		
400+33	RT	R5-1	DO NOT ENTER	6.3							MOUNT WITH R1-2
400+70	LT	W11-2	PEDESTRIAN TRAFFIC	6.3						16	
400+70	LT	W16-7pL	LEFT DIAGONAL ARROW PLAQUE	2.0							MOUNT WITH W11-2
401+55	LT	W3-2a	YIELD AHEAD	9.0						15	
401+55	RT	W3-2a	YIELD AHEAD	9.0						15	
402+80	LT	W2-6	CIRCULAR INTERSECTION	6.3						16	
402+80	LT	W13-1	ADVISORY SPEED (20 MPH)	2.3							MOUNT WITH W2-6
402+80	RT	W2-6	CIRCULAR INTERSECTION	6.3						16	
402+80	RT	W13-1	ADVISORY SPEED (20 MPH)	2.3							MOUNT WITH W2-6
404+05	LT	W12-2	LOW CLEARANCE (14 FT 0 IN)	9.0						17	
404+05	LT	W16-6pL	ARROW PLAQUE (ADVANCED LEFT)	3.0							MOUNT WITH W12-2

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FILE NAME = D:\BTR1-76C38-sht-schedule-01-05.dgn
 USER NAME = ldo
 MODEL NAME = D:\BTR1-76C38-sht-schedule-04
 PLOT SCALE = 1:1
 PLOT DATE = 10/1/2009

DESIGNED - LDC
 DRAWN -
 CHECKED - GEB
 DATE - 08/14/09

SCALE: NONE
 SHEET NO. 4 OF 5 SHEETS
 STA. ----- TO STA. -----

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	82-1-10N	ST. CLAIR	68	14
* 9166/9180			CONTRACT NO. 76C38	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		