SUMMARY OF QUANTITIES

			RURAL - PERRY COUNTY HBP FUNDING 80% FEDERAL; 20% STATE X071-2A SN 073-0037	
	CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
	70101855	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 (SPECIAL)	L SUM	1
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	3
	70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
	70106700	TEMPORARY RUMBLE STRIP	EACH	6
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
	70300100	SHORT - TERM PAVEMENT MARKING	FOOT	110
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1620
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	576
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1980
*	78200405	GUARDRAIL MARKERS	EACH	11
*	78200500	BARRIER WALL MARKERS	EACH	6
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	394
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2
*	86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1	EACH	1
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 2	EACH	1
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
	X0321781	MECHANICAL SPLICE	EACH	72
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22

*SPECIALTY ITEMS

FILE NAME c:\pw_work\PWIDOT\HALSTEADTW\dms49780\d978064_sht_misc.dgn	USER NAME = halsteadtw	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 865	SECTION 16B-2	COUNTY PERRY	TOTAL SHEETS 47 / SHEET NO. 4
	PLOT SCALE = 50.0000 ' / IN.	DRAWN	REVISED					CONTRACT NO. 78064	
78064/CADDSHEETS/D978064_SHT_MISC.DGN	PLOT DATE = 6/23/2009	CHECKED	REVISED		SCALE: SHEET NO. OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT	
		DATE	REVISED						