

SUMMARY OF QUANTITIES

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		NON-PARTICIPATING (100%) YOGO KANE COUNTY DIVISION OF TRANSPORTATION
						ROADWAY IOO0	CULVERT X028-2A	
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	30		
S		20101400	NITROGEN FERTILIZER NUTRIENT	POUND	74	74		
S		20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	74	74		
S		20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	74	74		
S		20101700	SUPPLEMENTAL WATERING	UNIT	12	12		
	•	20200100	EARTH EXCAVATION	CU YD	964	964		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1044	1044		
		20400800	FURNISHED EXCAVATION	CU YD	651	651		
	•	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	250	250		
		20800150	TRENCH BACKFILL	CU YD	333	333		
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	756	756		
S	•	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4117	4117		
	•	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	80	80		
S		25000210	SEEDING, CLASS 2A	ACRE	0.36	0.36		
S		25000310	SEEDING, CLASS 4	ACRE	0.47	0.47		
S		25100630	EROSION CONTROL BLANKET	SQ YD	4037	4037		
S	•	28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.77	0.77		
	•	28000400	PERIMETER EROSION BARRIER	FOOT	2913	2913		
	•	28000500	INLET AND PIPE PROTECTION	EACH	4	4		
		28100107	STONE RIPRAP, CLASS A4	SQ YD	134	40	94	
		28200200	FILTER FABRIC	SQ YD	134	40	94	
		31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	279	279		
		35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	296	296		
		35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	71	71		
		40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5		
		40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	2234	2234		
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	43	43		
	•	44000100	PAVEMENT REMOVAL	SQ YD	2078	2078		
	•	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	160	160		
		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2038	2038		
	•	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
	•	50105220	PIPE CULVERT REMOVAL	FOOT	139	139		
		51500100	NAME PLATES	EACH	1		1	
		54001000	BOX CULVERT END SECTIONS	EACH	2		2	
		54011111	PRECAST CONCRETE BOX CULVERT 11' X 11'	FOOT	72		72	
		54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	2		
		54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2		
		54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	2	2		
S	•	54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	2	2		
		55022500	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	69	69		
		55034500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	28	28		
		60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6	6		
	•	60100945	PIPE DRAINS 12"	FOOT	500	500		
		60107600	PIPE UNDERDRAINS 4"	FOOT	1248	1248		
S	•	60228120	MANHOLES, SANITARY, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1			1
		60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	4	4		

FILE NAME = PACBBEL WEST Projects \2009\1231256\es\Ingr\Plt\A\Design\Ugn\025\summary.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED - SBP	REVISED -
PLOT SCALE = NONE	DRAWN - TC	REVISED -
PLOT DATE = 8/20/2009	CHECKED - SBP	REVISED -
	DATE - January 2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 3	OF 37 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0110	01-00267-00-BR	KANE	37	3
CONTRACT NO. 83994				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				