

EARTHWORK, LANDSCAPING, EROSION CONTROL				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	0	30	30
NITROGEN FERTILIZER NUTRIENT	POUND	40	34	74
PHOSPHORUS FERTILIZER NUTRIENT	POUND	40	34	74
POTASSIUM FERTILIZER NUTRIENT	POUND	40	34	74
SUPPLEMENTAL WATERING	UNIT	7	5	12
EARTH EXCAVATION	CU YD	437	527	964
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	577	467	1044
FURNISHED EXCAVATION	CU YD	505	146	651
POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	125	125	250
TRENCH BACKFILL	CU YD	96	237	333
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	378	378	756
TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2178	1939	4117
EXPLORATION TRENCH, SPECIAL	FOOT	40	40	80
SEEDING, CLASS 2A	ACRE	0.18	0.18	0.36
SEEDING, CLASS 4	ACRE	0.27	0.20	0.47
EROSION CONTROL BLANKET	SQ YD	2214	1823	4037
TEMPORARY EROSION CONTROL SEEDING	ACRE	0.44	0.33	0.77
PERIMETER EROSION BARRIER	FOOT	1491	1422	2913
INLET AND PIPE PROTECTION	EACH	4	0	4
STONE RIPRAP, CLASS A4	SQ YD	5	129	134
FILTER FABRIC	SQ YD	5	129	134
TREE, AMELANCHIER X GRANDIFLORA (APPLE SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	1	1	2
TEMPORARY CLEAR WATER DIVERSION	L SUM	0	1	1
TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	2	6	8
SEEDING, SPECIAL	SQ YD	920	0	920
TURBIDITY CURTAIN	FOOT	0	176	176

BASE COURSES				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	164	115	279
AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	296	0	296
HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	71	0	71
AGGREGATE SUBGRADE 12"	SQ YD	1697	2274	3971

SURFACE COURSES, PAVEMENTS REHABILITATION AND SHOULDERS				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
BITUMINOUS MATERIALS (PRIME COAT)	TON	3	2	5
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	1127	1107	2234
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	43	0	43
PAVEMENT REMOVAL	SQ YD	1039	1039	2078
DRIVEWAY PAVEMENT REMOVAL	SQ YD	160	0	160
HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	995	1043	2038
TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	0	1
TEMPORARY ACCESS (ROAD)	EACH	1	0	1
TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	0	2

STRUCTURES				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
REMOVAL OF EXISTING STRUCTURES	EACH	0	1	1
PIPE CULVERT REMOVAL	FOOT	139	0	139
NAME PLATES	EACH	0	1	1
BOX CULVERT END SECTIONS	EACH	2	0	2
PRECAST CONCRETE BOX CULVERT 11' X 11'	FOOT	0	72	72
PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	0	2
PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	0	2
GRATING FOR CONCRETE FLARED END SECTION	EACH	2	0	2
GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	2	0	2
STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 42"	FOOT	69	0	69
STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 38, RISE 24	FOOT	28	0	28

MISCELLANEOUS CONSTRUCTION				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	2	6
PIPE DRAINS 12"	FOOT	250	250	500
PIPE UNDERDRAINS 4"	FOOT	520	728	1248
INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	2	2	4
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	331	444	775
STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	0	75	75
TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	0	4
TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2	4
GUARDRAIL REMOVAL	FOOT	88	266	354
STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	117	8	125
MOBILIZATION	L SUM	1	0	1
TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0	1
CHANGEABLE MESSAGE SIGN	CAL MO	1	1	2
TEMPORARY INFORMATION SIGNS	EACH	1	1	2
CONSTRUCTION LAYOUT	L SUM	1	0	1
FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	9	8	17

SANITARY SEWER CONSTRUCTION				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0	1
SANITARY MANHOLES TO BE REMOVED	EACH	1	0	1
SELECT GRANULAR BACKFILL	CU YD	65	149	214
GATE VALVE, 6"	EACH	1	0	1
DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	632	632	1264
ABANDON AND FILL EXISTING SANITARY SEWER SYSTEM	EACH	1	1	2
AIR RELEASE VALVE	EACH	1	0	1
POLYETHYLENE ENCASEMENT	FOOT	330	383	713
SANITARY SEWER, SPECIAL	FOOT	330	383	713

SIGNING AND PAVEMENT MARKING				
PAY ITEM	UNIT	STA 306+50 TO STA 310+75	STA 310+75 TO STA 314+96.72	TOTAL
MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	15	7	22
EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1700	1594	3294
TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	4

FILE NAME = P:\CBBEL WEST Projects\2809\123135\KasImp\PH\Design\Dgn\95Schedule.dgn



USER NAME = *USER*	DESIGNED - SBP	REVISED -
PLOT SCALE = NONE	DRAWN - TC	REVISED -
PLOT DATE = 8/20/2009	CHECKED - SBP	REVISED -
	DATE - January 2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE	SHEET NO.	OF	TOTAL SHEETS
NONE	5	OF	37

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0110	01-00267-00-BR	KANE	37	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

CONTRACT NO. 83994