

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: Y047

ITEM #	ITEM DESCRIPTION	UNITS	BRIDGE 99 QTY	BRIDGE 104 QTY	BRIDGE 107 QTY	TOTAL QTY
M2010110*	TREE REMOVAL (6-15 UNIT DIAMETER)	UNIT	236	6	0	242
M2010210*	TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNIT	124	0	0	124
M2020010*	EARTH EXCAVATION	CU M	1,183	0	0	1,183
M2040800	FURNISHED EXCAVATION	CU M	0	0	750	750
M2060310*	QUARRY RUN GRANULAR EMBANKMENT	CU M	0	0	86	86
M2070220	POROUS GRANULAR EMBANKMENT	CU M	95	5	0	100
M2090110	POROUS GRANULAR BACKFILL	CU M	0	0	420	420
M2500100	SEEDING, CLASS 1	HA	0.32	0.00	0.00	0.32
M2500310	SEEDING, CLASS 4	HA	0.00	0.15	0.27	0.42
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	32	15	27	74
M2500500	PHOSPHOROUS FERTILIZER NUTRIENT	KG	32	15	27	74
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	32	15	27	74
M2510115	MULCH, METHOD 2	HA	0.32	0.15	0.27	0.74
M2510800	EROSION CONTROL MAT	SQ M	3,200	140	200	3,540
M2800400	PERIMETER EROSION BARRIER	METER	350	160	120	630
M2810109	STONE RIPRAP, CLASS A5	SQ M	630	0	23	653
M2810709	STONE DUMPED RIPRAP, CLASS A5	SQ M	0	0	200	200
M2811700*	RIP-RAP, SPECIAL	M TON	410	0	0	410
M2820200	FILTER FABRIC	SQ M	630	0	200	830
M3010300*	SHAPING AND GRADING ROADWAY	UNITS	0	11	21	32
M3511200	AGGREGATE BASE COURSE, TYPE B 200MM	SQ M	252	830	1,476	2,558
M4020050*	AGGREGATE SURFACE COURSE, TYPE A, 50 MM	SQ M	0	830	1,476	2,306
M4060200	BITUMINOUS MATERIALS, PRIME COAT	M TON	5	0	0	5
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	32	0	0	32
5010100*	REMOVAL OF EXISTING STRUCTURES	EACH	0	0	1	1
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	0	1	0	1
M2013300*	CONCRETE REMOVAL (SPECIAL)	SQ M	24.3	0.0	0.0	24.3
M5030350	CONCRETE STRUCTURES	CU M	89.9	2.4	0.0	92.3
MX033694*	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125MM)	SQ. M.	38.9	0	0	38.9
MX033693*	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 125MM)	SQ. M.	44.4	0	0	44.4
M5070105	TREATED TIMBER	CU M	0.0	3.0	0.0	3.0
M5070305	HARDWARE	KG	0	126	0	126
M5080105	REINFORCEMENT BARS	KG	4,220	236	0	4,456
M5120176	FURNISHING METAL SHELL PILES, 356MM X 6.35MM	METER	66	0	0	66
51203200	TEST PILE METAL SHELLS	EACH	2	0	0	2
M5120335*	DRIVING PILES	METER	66	0	0	66
51500110*	NAME PLATES (SPECIAL)	EACH	1	1	1	3
M5210020	ANCHOR BOLTS, M20	EACH	0	20	0	20
M5210022	ANCHOR BOLTS, M24	EACH	32	0	0	32
54001000	BOX CULVERT END SECTIONS	EACH	0	0	2	2
M5401160	PRECAST CONCRETE BOX CULVERT 3.0M X 2.4M	METER	0	0	18	18
M5403220	EXPANSION BOLTS, M20	EACH	16	0	0	16
60255500	MANHOLES TO BE ADJUSTED	EACH	1	0	0	1
M6650100	WOVEN WIRE FENCE, 1.2METER	METER	0	0	116	116
M6650350	BARBED WIRE FENCE REMOVAL	METER	0	0	116	116
67100100	MOBILIZATION	L SUM	1	0	0	1
70101700*	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0	0	1
78200100	UNIDIRECTIONAL PRISMATIC BARRIER REFLECTORS	EACH	12	12	12	36
MX030570*	PNEUMATIC BRIDGE SUPERSTRUCTURE	SQ M	504	0	0	504
MZ078000*	WOOD RAIL	METER	10	10	116	136
MZ064600*	SELECTIVE CLEARING	HA	0.01	0.15	0.27	0.43
XX008022*	MASONRY CLEANING AND TUCK POINTING	L SUM	0	1	0	1
XU323817*	SEDIMENT CONTROL, SILT CURTAIN	EACH	3	0	1	4
X2800500*	INLET PROTECTION, SPECIAL	EACH	3	0	0	3
X5020501*	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1	EACH	1	0	0	1
X5020502*	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 2	EACH	0	0	1	1
XX009023*	REMOVE & RESET EXISTING STEEL STRINGER ASSY.	EACH	0	1	0	1
M5090505*	BICYCLE RAILING (SPECIAL)	METER	0	0	26	26
Z0018965	DRILL AND GROUT BARS	EACH	118	156	0	274

Δ SPECIALTY ITEMS

REVISIONS		
NO.	ITEM	DATE

PLOTTING SCALE: 1 : 1
DRAWN BY: REK
CHECKED BY:
DATE: JUNE, 2009



7282 Argus Drive Rockford, Illinois 61107-6837
 (815) 398-2332 FAX (815) 398-2496
 Design Firm License: Illinois 164-000816
 Copyright 2009 By McClure Engineering Associates, Inc.

SUMMARY OF QUANTITIES

PECATONICA PRAIRIE PATH

STEPHENSON COUNTY SECTION 08-P4000-00-BT

JOB NUMBER: 04-28-98-037