PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"

LOCATION	OFFSET	LT/RT	54200640 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"
	FEET		FOOT
STA. 193+17.11 TO STA. 193+51.11, ENTRANCE	30.7' TO 30.9'	RT	34
STA. 226+73.03 TO STA. 227+15.03, ENTRANCE	35.7'	RT	42
STA. 233+55.57 TO STA. 234+05.57, ENTRANCE	33.2' TO 34.7'	LT	50
STA. 235+17.41 TO STA. 235+59.41, ENTRANCE	33.5' TO 32.8'	RT	42
		TOTAL	168

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"

LOCATION	OFFSET	LT/RT	54200643 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"
	FEET		FOOT
STA. 153+66.69 TO STA. 154+06.69, ENTRANCE	36.3' TO 35.6'	RT	40
STA. 173+07.30 TO STA. 173+52.99, ENTRANCE	35.4' TO 40.8'	RT	46
STA. 173+20.08 TO STA. 173+56.08, ENTRANCE	31.0' TO 33.0'	LT	36
STA. 185+97.34 TO STA. 186+35.34, ENTRANCE	27.4' TO 26.7'	LT	38
STA. 202+00.53 TO STA. 202+32.53, ENTRANCE	28.3'	LT	32
STA. 204+55.45 TO STA. 204+85.45, ENTRANCE	28.3'	LT	30
STA. 221+39.49 TO STA. 221+83.49, ENTRANCE	32.5' TO 33.0'	LT	44
		TOTAL	266

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"

LOCATION	OFFSET	LT/RT	54200649 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"
	FEET		FOOT
STA. 131+91.55 TO STA. 132+91.55, AT MCKINLEY RD. INT.	32.3' TO 33.4'	LT	100
STA. 131+95.28 TO STA. 132+95.28, AT MCKINLEY RD. INT.	31.4' TO 32.3'	RT	100
STA. 215+32.66 TO STA. 215+74.59, ENTRANCE	33.1' TO 35.5'	LT	42

PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"

LOCATION	OFFSET	LT/RT	54201483 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"
	FEET		FOOT
CL STA. 174+02.87, CROSS-ROAD (STA. 174+01.31 LT & STA. 174+04.97 RT)	24.9' LT TO 33.2' RT		58.4
CL STA. 174+02.87, CROSS-ROAD (ADDITIONAL QUANTITY FOR EXTENSION TO THE EAST	33.2' RT TO 65.9' RT	RT	25
		TOTAL	83

PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"

LOCATION	OFFSET	LT/RT	54201489 PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"
	FEET		FOOT
CL STA. 179+53.72, CROSS-ROAD (STA. 179+54.03 LT & STA. 179+53.33 RT)	24.5' LT TO 31.6' RT		56.2
		TOTAL	56

PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"

LOCATION	OFFSET	54201495 PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"
	FEET	FOOT
CL STA. 216+79.11, CROSS-ROAD (STA. 216+81.11 LT & STA. 216+76.97 RT)	28.6' LT TO 30.5' RT	59.3
	TOTAL	60

PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 36"

LOCATION	OFFSET	54201501 PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 36"
	FEET	FOOT
CL STA. 135+96.54, CROSS-ROAD (STA. 135+95.83 LT & STA. 135+97.28 RT)	35.1' LT TO 36.9' RT	72
	TOTAL	72

METAL END SECTIONS 18"

LOCATION	OFFSET	LT/RT	54215559 METAL END SECTIONS 18"
	FEET		EACH
STA. 174+01.31	24.9'	LT	1
STA. 174+04.97	33.2'	RT	1
		TOTAL	2

METAL END SECTIONS 30"

LOCATION	OFFSET	LT/RT	54215565 METAL END SECTIONS 30"
	FEET		EACH
STA. 216+76.97	30.5'	RT	1
STA. 216+81.11	28.6'	LT	1
		TOTAL	2

PIPE CULVERT REMOVAL

LOCATION	SIZE (INCHES)	TYPE	50105220 PIPE CULVERT REMOVAL
			FOOT
STA. 135+96.54, CROSS-ROAD	36	CMP	67.7
STA. 173+38.08, LT	18	CMP	24.0
STA. 174+02.87, CROSS-ROAD	15		90.0
STA. 179+53.72, CROSS-ROAD	24	CMP	48.4
STA. 186+16.34, LT	10	STEEL	30.3
STA. 193+34.11, RT	10		19.3
STA. 202+16.53, LT	14	CMP	24.2
STA. 204+70.44, LT	24	CMP	30.2
STA. 215+52.06, LT	24	CMP	24.2
STA. 216+79.11, CROSS-ROAD	30	CMP	59.5
STA. 221+61.50, LT	12	CMP	32.5
		TOTAL	450

METAL END SECTIONS 24"

LOCATION	OFFSET	LT/RT	54215559 METAL END SECTIONS 24"
	FEET		EACH
STA. 131+91.55, AT MCKINLEY RD. INT.	32.3'	LT	1
STA. 132+91.55, AT MCKINLEY RD. INT.	33.4'	LT	1
STA. 131+95.28, AT MCKINLEY RD. INT.	31.4'	RT	1
STA. 132+95.28, AT MCKINLEY RD. INT.	32.3'	RT	1
STA. 179+53.33	31.6'	RT	1
STA. 179+54.03	24.5'	LT	1
		TOTAL	6

METAL END SECTIONS 36"

LOCATION	OFFSET	LT/RT	54215571 METAL END SECTIONS 36"
	FEET		EACH
STA. 135+95.83	35.1'	LT	1
STA. 135+97.28	36.9'	RT	1
		TOTAL	2

MAURER & STUTZ, INC. CONSULTING ENGINEERS
7615 NORTH HARKER DRIVE
PEORIA, ILLINOIS 61615
PH. (309) 693-7615
FAX (309) 693-7616