

# SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 22	05-00907-00-BR	CHAMPAIGN	36	3
STA.	TO STA.			
F.H.W.A. REG.	ILLINOIS	PROJECT		

NO.	ITEM	UNIT	MAJOR BRIDGE FUNDS	LOCAL FUNDS	TOTAL
			STA. 8+54 TO STA. 11+46 CODE X081-2A	STA. 7+50 TO STA. 8+54 STA. 11+46 TO STA. 14+53.21 CODE A000-2A-K000-2A	
20100500	TREE REMOVAL, ACRES	ACRES	0.01	0.17	0.18
20200100	EARTH EXCAVATION	CU. YD.	0	296	296
20400800	FURNISHED EXCAVATION	CU. YD.	0	488	488
25000200	SEEDING CLASS 2	ACRE	0	1.01	1.01
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	91	91
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	91	91
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	91	91
25100115	MULCH METHOD 2	ACRE	0	1.01	1.01
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	0	600	600
28000300	TEMPORARY DITCH CHECKS	EACH	0	10	10
28000400	PERIMETER EROSION BARRIER	FOOT	0	822	822
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ. YD.	0	1009	1009
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	73	378	451
40600300	AGGREGATE (PRIME COAT)	TON	1.5	2.6	4.1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	0	120	120
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	106	110	216
44000100	PAVEMENT REMOVAL	SQ. YD.	0	954	954
48101500	AGGREGATE SHOULDERS, TYPE B-6"	SQ. YD.	0	357	357
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1.0
50200100	STRUCTURE EXCAVATION	CU. YD.	219	0	219
50300225	CONCRETE STRUCTURES	CU. YD.	189.8	0	189.8
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ. FT.	8,713	0	8,713
50800105	REINFORCEMENT BARS	POUND	13,420	0	13,420
*50900205	STEEL RAILING, TYPE S-1	FOOT	584	0	584
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	2,172	0	2,172
51202305	DRIVING PILES	FOOT	2,172	0	2,172
51203600	TEST PILE STEEL HP 12X53	EACH	3	0	3
51204650	PILE SHOES	EACH	44	0	44
51500100	NAME PLATES	EACH	1	0	1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	969	0	969
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU. YD.	0	51	51
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	0	300	300
*63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	0	4	4
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	0	4	4

NO.	ITEM	UNIT	MAJOR BRIDGE FUNDS	LOCAL FUNDS	TOTAL
			STA. 8+54 TO STA. 11+46 CODE X081-2A	STA. 7+50 TO STA. 8+54 STA. 11+46 TO STA. 14+53.21 CODE A000-2A-K000-2A	
63200310	GUARDRAIL REMOVAL	FOOT	0	225	225
66502200	WOVEN WIRE FENCE (SPECIAL)	FOOT	0	773	773
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	0	730	730
67100100	MOBILIZATION	L. SUM	0.7	0.3	1.0
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	584	823	1407
XX004565	GROUTED RIPRAP	SQ. YD.	1053	0	1053
XX004566	CONCRETE CUT-OFF WALL	CU. YD.	7.2	0	7.2

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES  
SECTION: 05-00907-00-BR  
CHAMPAIGN COUNTY  
STATION 10+00