

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	SAFETY CODE	
		CONSTRUCTION CODE	2A
		UNIT	1000 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	59
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	49
25200100	SODDING	SQ YD	49
25200200	SUPPLEMENTAL WATERING	UNIT	1
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	45
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,921
40600300	AGGREGATE (PRIME COAT)	TON	101
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9
* 40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	1,685
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600990	TEMPORARY RAMP	SQ YD	1,777
* 40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4,391
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	15,114
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	24,067
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	762
* 44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1,111
44003100	MEDIAN REMOVAL	SQ FT	41
44200990	CLASS B PATCHES, TYPE I, 12 INCH	SQ YD	8
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	369
44213200	SAW CUTS	FOOT	1,137
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	27,990
* 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3
* 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	17
* 60406500	FRAMES AND LIDS, SPECIAL	EACH	11
* 60406510	FRAMES AND LIDS (SALVAGED)	EACH	10
* 60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	384
* 60620700	CONCRETE MEDIAN, TYPE SB-9.06 (SPECIAL)	SQ FT	1,490
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,968
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3,984
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	372

\*SEE SPECIAL PROVISIONS

CODE NO.	ITEM	SAFETY CODE	
		CONSTRUCTION CODE	2A
		UNIT	1000 TOTAL QUANTITY
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,072
△ * 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	312
△ * 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22,786
△ * 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,136
△ * 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,748
△ * 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	372
△ * 88600400	DETECTOR LOOP, SPECIAL	FOOT	110
△ * 89502380	REMOVE EXISTING HANDHOLE	EACH	1
△ * 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2
* X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28
* XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	83
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0017202	DOWEL BARS 1 1/2"	EACH	610
* XX008143	TEMPORARY RAMP, SPECIAL	EACH	75

\*SEE SPECIAL PROVISIONS △ SPECIALTY ITEMS

FILE NAME = p:\00010470\Plans\summary.dgn  
 PLOT DATE = 7/16/2009 1:17:33 PM

DESIGNED - R.L.H.      REVISED -  
 DRAWN - J.L.B.        REVISED -  
 CHECKED - J.T.P.      REVISED -  
 DATE - 6-09            REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE      SHEET NO. 3 OF 27 SHEETS      STA.      TO STA.

F.A.U. RTE. 7138	SECTION 09-00281-00-RS	COUNTY CHAMPAIGN	TOTAL SHEETS 27	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS			CONTRACT NO. 91408	
FED. AID PROJECT ARA-5181 (046)				