

# SCHEDULE OF QUANTITIES

**20200100  
EARTH EXCAVATION**

STATION	TO STATION	CU YD
KIRBY AVENUE 13+31.9 LT. & RT.	15+38.2 LT. & RT.	59
TOTAL		59

**21101625  
TOPSOIL FURNISH AND PLACE, 6"**

LOCATION	SO YD	
KIRBY AVENUE CURB AND GUTTER REPLACEMENT LOCATIONS	49	
TOTAL		49

**25200100  
SODDING**

LOCATION	SO YD	
KIRBY AVENUE CURB AND GUTTER REPLACEMENT LOCATIONS	49	
TOTAL		49

**25200200  
SUPPLEMENTAL WATERING**

LOCATION	UNIT	
KIRBY AVENUE CURB AND GUTTER REPLACEMENT LOCATIONS	1	
TOTAL		1

**40201000  
AGGREGATE FOR TEMPORARY ACCESS**

LOCATION	TON	
KIRBY AVENUE CURB AND GUTTER REPLACEMENT LOCATIONS	45	
TOTAL		45

**70300100  
SHORT-TERM PAVEMENT MARKING**

LOCATION	FOOT	
KIRBY AVENUE AND PROSPECT AVENUE AFTER HMA SURFACE REMOVAL	3984	
AFTER LEVELING BINDER PLACEMENT	3984	
TOTAL		7968

**70300520  
PAVEMENT MARKING TAPE, TYPE III 4"**

LOCATION	FOOT	
KIRBY AVENUE AND PROSPECT AVENUE AFTER HMA SURFACE COURSE PLACEMENT	3984	
TOTAL		3984

**70300570  
PAVEMENT MARKING TAPE, TYPE III 24"**

LOCATION	FOOT	
KIRBY AVENUE AND PROSPECT AVENUE AFTER HMA SURFACE COURSE PLACEMENT AT SAME LOCATIONS AS FINAL MARKINGS	372	
TOTAL		372

**70301000  
WORK ZONE PAVEMENT MARKING REMOVAL**

LOCATION	SO FT	
KIRBY AVENUE AND PROSPECT AVENUE REMOVAL OF PAVEMENT MARKING TAPE, TYPE III 4" AND 24"	2072	
TOTAL		2072

**TEMPORARY RAMP, SPECIAL**

LOCATION	EACH	
KIRBY AVENUE AND PROSPECT AVENUE AT EXISTING DRIVEWAYS	75	
TOTAL		75

LOCATION	REMOVAL SCHEDULE OF QUANTITIES											
	44000157 HOT-MIX ASPHALT SURFACE REMOVAL, 2" (SQ YD)	44000162 HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" (SQ YD)	44000500 COMBINATION CURB AND GUTTER REMOVAL (FOOT)	44002020 CONCRETE MEDIAN SURFACE REMOVAL (SQ FT)	44003100 MEDIAN REMOVAL (SQ FT)	44200990 CLASS B PATCHES, TYPE I, 12 INCH (SQ YD)	44200994 CLASS B PATCHES, TYPE II, 12 INCH (SQ YD)	44213200 SAW CUTS (FOOT)	89502380 REMOVE EXISTING HANDHOLE (EACH)	89502385 REMOVE EXISTING CONCRETE FOUNDATION (EACH)	XX001135 PAVEMENT PATCHING SPECIAL (SQ YD)	Z0017202 DOWEL BARS 1 1/2" (EACH)
<b>KIRBY AVENUE</b>												
SHEET NO. 11												
STA. 7+53.00 TO STA. 11+50.00	----	2340.2	72.4	----	----	----	48.0	150	----	----	12.3	80
SHEET NO. 12												
STA. 11+50.00 TO STA. 17+00.00	----	3373.6	418.0	1111.2	----	----	22.0	71	----	----	12.3	38
SHEET NO. 13												
STA. 17+00.00 TO STA. 22+50.00	----	3055.3	171.2	----	----	----	74.6	218	----	----	10.0	120
SHEET NO. 14												
STA. 22+50.00 TO STA. 28+00.00	----	3164.5	100.3	----	41.0	8.0	----	52	1	2	5.6	12
SHEET NO. 15												
STA. 28+00.00 TO STA. 33+50.00	----	3058.8	----	----	----	----	53.2	146	----	----	10.0	80
SHEET NO. 16												
STA. 33+50.00 TO STA. 39+00.00	----	3174.1	----	----	----	----	21.4	72	----	----	9.0	40
SHEET NO. 17												
STA. 39+00.00 TO STA. 44+50.00	----	3186.0	----	----	----	----	53.2	146	----	----	8.2	80
SHEET NO. 18												
STA. 44+50.00 TO STA. 50+00.00	224.6	2714.7	----	----	----	----	96.0	282	----	----	5.4	160
SHEET NO. 19												
STA. 50+00.00 TO STA. 55+40.00	3497.3	----	----	----	----	----	----	----	----	----	5.9	----
SHEET NO. 20												
STA. 55+40.00 TO STA. 59+00.00 & STA. 599+25.00 TO STA. 600+75.00	3248.9	----	----	----	----	----	----	----	----	----	0.5	----
SHEET NO. 21												
STA. 59+00.00 TO STA. 62+70.00	2217.8	----	----	----	----	----	----	----	----	----	----	----
<b>PROSPECT AVENUE</b>												
SHEET NO. 22												
STA. 593+64.00 TO STA. 599+25.00	3509.1	----	----	----	----	----	----	----	----	----	3.6	----
SHEET NO. 23												
STA. 600+75.00 TO STA. 604+71.00	2416.1	----	----	----	----	----	----	----	----	----	----	----
TOTALS	15113.8	24067.2	761.9	1111.2	41.0	8.0	368.4	1137	1	2	82.8	610

FILE NAME = p:\c0010470\plans\sheets\schedule.dgn  
 PLOT DATE = 7/16/2009 10:44:31 AM

DESIGNED - R.L.H.	REVISED -
DRAWN - J.L.B.	REVISED -
CHECKED - J.T.P.	REVISED -
DATE - 6-09	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE : NONE SHEET NO. 4 OF 27 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7138	09-00281-00-RS	CHAMPAIGN	27	4
FED. ROAD DIST. NO. ILLINOIS			CONTRACT NO. 91408	
FED. AID PROJECT ARA-5181 (046)				