

SCHEDULE OF QUANTITIES

LOCATION	PROPOSED SCHEDULE OF QUANTITIES												
	40600100 BITUMINOUS MATERIALS (PRIME COAT) (0.10 GAL/SY) (GALLON)	40600300 AGGREGATE (PRIME COAT) (TON)	40600400 MIXTURE FOR CRACKS JOINTS AND FLANGEWAYS (TON)	40600845 POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90 (1 1/4" THICK) (TON)	40600990 TEMPORARY RAMP (SQ YD)	40603545 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (2" THICK) (TON)	44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT (FOOT)	60406000 FRAMES AND LIDS, TYPE 1, OPEN LID (EACH)	60406100 FRAMES AND LIDS, TYPE 1, CLOSED LID (EACH)	60406500 FRAMES AND LIDS, SPECIAL (EACH)	60406510 FRAMES AND LIDS (SALVAGED) (EACH)	60604200 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL) (FOOT)	60620700 CONCRETE MEDIAN, TYPE SB-9.06 (SQ FT)
KIRBY AVENUE													
SHEET NO. 11													
STA. 7+53.00 TO STA. 11+50.00	234	6	0.5	164	154	262	1588	1	2	1	2	72.4	----
SHEET NO. 12													
STA. 11+50.00 TO STA. 17+00.00	337	9	0.7	236	153	378	1752	----	1	2	3	39.7	1489.8
SHEET NO. 13													
STA. 17+00.00 TO STA. 22+50.00	306	8	0.6	214	31	342	2200	----	4	1	----	171.2	----
SHEET NO. 14													
STA. 22+50.00 TO STA. 28+00.00	317	8	0.7	222	59	355	2200	----	2	----	----	100.3	----
SHEET NO. 15													
STA. 28+00.00 TO STA. 33+50.00	306	8	0.6	214	28	343	2200	----	2	2	1	----	----
SHEET NO. 16													
STA. 33+50.00 TO STA. 39+00.00	318	8	0.7	222	58	356	2200	----	3	2	----	----	----
SHEET NO. 17													
STA. 39+00.00 TO STA. 44+50.00	319	8	0.7	223	58	357	2200	----	----	2	2	----	----
SHEET NO. 18													
STA. 44+50.00 TO STA. 50+00.00	294	8	0.6	190	27	329	2282	----	----	1	2	----	----
SHEET NO. 19													
STA. 50+00.00 TO STA. 55+40.00	350	9	0.7	----	166	392	3240	1	2	----	----	----	----
SHEET NO. 20													
STA. 55+40.00 TO STA. 59+00.00 & STA. 599+25.00 TO STA. 600+75.00	325	8	0.7	----	344	364	2520	----	----	----	----	----	----
SHEET NO. 21													
STA. 59+00.00 TO STA. 62+70.00	222	6	0.5	----	105	249	1780	----	----	----	----	----	----
PROSPECT AVENUE													
SHEET NO. 22													
STA. 593+64.00 TO STA. 599+25.00	351	9	0.7	----	323	393	2244	1	1	----	----	----	----
SHEET NO. 23													
STA. 600+75.00 TO STA. 604+71.00	242	6	0.5	----	271	271	1584	----	----	----	----	----	----
TOTALS	3921	101	8.2	1685	1777	4391	27990	3	17	11	10	383.6	1489.8

FILE NAME =
p:\c0010470\plans\sheets\schedule.dgn
PLOT DATE =
7/16/2009 10:44:31 AM

DESIGNED - R.L.H.	REVISED -
DRAWN - J.L.B.	REVISED -
CHECKED - J.T.P.	REVISED -
DATE - 6-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE : NONE SHEET NO. 5 OF 27 SHEETS STA. TO STA.

F.A.U. RTE. 7138	SECTION 09-00281-00-RS	COUNTY CHAMPAIGN	TOTAL SHEETS 27	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ARA-5181 (046)			CONTRACT NO. 91408	