

SCHEDULE OF QUANTITIES

LOCATION	PAVEMENT MARKING SCHEDULE OF QUANTITIES									
	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"				78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"		78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	
	TURN ARROWS (SQ FT)	SKIP-DASH YELLOW (FOOT)	SOLID YELLOW (FOOT)	DOUBLE YELLOW NARROW (FOOT)	SKIP-DASH WHITE (FOOT)	SOLID WHITE (FOOT)	CROSSWALK WHITE (FOOT)	DIAGONAL YELLOW (FOOT)	CROSSWALK WHITE (FOOT)	STOP BAR WHITE (FOOT)
KIRBY AVENUE										
SHEET NO. 11 STA. 7+53.00 TO STA. 11+50.00	----	----	----	1198	180	----	102	81	----	18
SHEET NO. 12 STA. 11+50.00 TO STA. 17+00.00	----	----	445	785	220	----	203	88	84	35
SHEET NO. 13 STA. 17+00.00 TO STA. 22+50.00	----	----	----	1810	250	----	103	113	----	18
SHEET NO. 14 STA. 22+50.00 TO STA. 28+00.00	----	----	----	1925	220	----	283	112	102	76
SHEET NO. 15 STA. 28+00.00 TO STA. 33+50.00	----	----	----	1809	250	----	----	107	----	----
SHEET NO. 16 STA. 33+50.00 TO STA. 39+00.00	----	----	----	1809	220	----	----	103	----	----
SHEET NO. 17 STA. 39+00.00 TO STA. 44+50.00	----	----	----	1809	240	----	----	107	----	----
SHEET NO. 18 STA. 44+50.00 TO STA. 50+00.00	----	----	----	2200	280	----	----	129	----	----
SHEET NO. 19 STA. 50+00.00 TO STA. 55+40.00	93.6	140	768	436	250	57	----	66	----	27
SHEET NO. 20 STA. 55+40.00 TO STA. 59+00.00 & STA. 599+25.00 TO STA. 600+75.00	78.0	----	509	52	180	278	349	22	396	166
SHEET NO. 21 STA. 59+00.00 TO STA. 62+70.00	31.2	----	237	1007	180	74	----	149	----	----
PROSPECT AVENUE										
SHEET NO. 22 STA. 593+64.00 TO STA. 599+25.00	62.4	110	390	894	250	101	96	54	----	16
SHEET NO. 23 STA. 600+75.00 TO STA. 604+71.00	46.8	----	----	875	170	178	----	35	----	16
SUB-TOTAL	312.0	250	2349	16609	2890	688	1136	1166	582	372
TOTAL	312.0			22786			1136	1748		372

FILE NAME =
p:\c0010470\plans\sheets\schedule.dgn
PLOT DATE =
7/16/2009 10:44:32 AM

DESIGNED - R.L.H.	REVISED -
DRAWN - J.L.B.	REVISED -
CHECKED - J.T.P.	REVISED -
DATE - 6-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE : NONE SHEET NO. 6 OF 27 SHEETS STA. TO STA.

F.A.U. RTE. 7138	SECTION 09-00281-00-RS	COUNTY CHAMPAIGN	TOTAL SHEETS 27	SHEET NO. 6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ARA-5181 (046)			CONTRACT NO. 91408	