

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
20200100	Earth Excavation	Cu.Yd.	499
20200500	Earth Excavation (Widening)	Cu.Yd.	34
25001000	Seeding Class 2, (Special)	Acre	0.2
25101005	Heavy Duty Excelsior Blanket	Sq. Yd.	690
28000250	Temporary Erosion Control Seeding	Pound	20
28000300	Temporary Ditch Checks	Each	2
28000400	Perimeter Erosion Barrier	Feet	935
35600712	Hot-Mix Asphalt Base Course Widening, 9"	Sq. Yd.	312
35800100	Preparation of Base	Sq.Yd.	2396
35800200	Aggregate Base Repair	Ton	111
40200800	Aggregate Surface Course, Type B	Ton	71
40600100	Bituminous Materials (Prime Coat)	Gal.	4376
40600300	Aggregate (Prime Coat)	Ton	64
40600400	Mixture for Cracks, Joints, and Flangeways	Ton	7
40600625	Leveling Binder (Machine Method) N50	Ton	1973
40600982	Hot-Mix Asphalt Surface Removal-Butt Joint	Sq. Yd.	146
40600990	Temporary Ramp	Sq.Yd.	69
40603080	Hot-Mix Asphalt Binder Course, IL19.0, N50	Ton	560
40603510	Polymerized Hot-Mix Asphalt Surface Course, Mix " C", N50	Ton	3400
40800010	Bituminous Materials (Prime Coat)	Gal.	1345
40800030	Aggregate (Prime Coat)	Ton	11
40800050	Incidental Hot-Mix Asphalt Surfacing	Ton	421
44000152	Hot-Mix Asphalt Surface Removal, 3/4"	Sq.Yd.	37191
44000155	Hot-Mix Asphalt Surface Removal, 1 1/2"	Sq.Yd.	3699
44000400	Gutter Removal	Feet	925
44200970	Class B Patches, Type II, 10"	Sq.Yd.	397
44200994	Class B Patches, Type II, 12"	Sq.Yd.	212
44213200	Saw Cuts	Feet	2979
44300900	Strip Reflective Crack Control Treatment, System A	Feet	16937
48101200	Aggregate Shoulders, Type B	Ton	1039
48203029	Hot-Mix Asphalt Shoulders, 8"	Sq.Yd.	2047
60600095	Class SI Concrete (Outlet)	Cu.Yd.	0.46
67100100	Mobilization	LS	1
70100450	Traffic Control and Protection Standard, 701201	LS	1
70100460	Traffic Control and Protection Standard, 701306	LS	1
70100500	Traffic Control and Protection Standard, 701326	LS	1
70100600	Traffic Control and Protection Standard, 701336	LS	1
70300100	Short -Term Pavement Marking	Feet	3546
70300220	Temporary Pavement Marking - Line 4"	Feet	53345
70301000	Work Zone Pavement Marking Removal	Sq. Ft.	492
* 78000200	Thermoplastic Pavement Marking - Line 4"	Feet	53345
* 78100100	Raised Reflective Pavement Marker	Each	197
Z0017200	Dowel Bars, 1 1/4"	Each	896
Z0017202	Dowel Bars, 1 1/2"	Each	416

* SPECIALTY ITEMS

Prepared by: Vermilion County Highway Dept. 2732 Batestown Road Oakwood, Illinois 61858	DENMARK RD. (C.H. 20) 2009 RESURFACING SECTION 07-00160-00-RS	SHEET 2
		OF 71
		June 29, 2009