

**SCHEDULE OF QUANTITIES**

**INCIDENTAL HOT-MIX ASPHALT SURFACING 40800050, CONTINUED**

LT 223+35	ENTRANCE	FE	AGGREGATE	1.5
LT 224+24	INTERSECTION	2300N	BITUMINOUS	41.2
RT 227+96	ENTRANCE	FE	DIRT	1.8
RT 230+31	ENTRANCE	PE	BITUMINOUS	1.1
RT 230+40	MBTO		AGGREGATE	2.0
LT 232+04	ENTRANCE	FE	AGGREGATE	1.5
RT 232+66	ENTRANCE	FE	AGGREGATE	1.8
LT 233+78	MBTO		BITUMINOUS	2.0
LT 234+06	ENTRANCE	PE	BITUMINOUS	2.6
RT 234+28	ENTRANCE	FE	AGGREGATE	1.5
RT 236+12	MBTO		AGGREGATE	2.0
LT 236+17	ENTRANCE	FE	AGGREGATE	2.2
RT 236+30	ENTRANCE	PE	AGGREGATE	2.9
RT 238+06	ENTRANCE	PE	AGGREGATE	3.9
LT 238+32	ENTRANCE	FE	AGGREGATE	1.3
RT 238+33	MBTO		AGGREGATE	2.0
RT 240+58	ENTRANCE	PE	AGGREGATE	2.5
RT 241+00	MBTO		AGGREGATE	2.0
LT 242+10	ENTRANCE	FE	AGGREGATE	2.2
RT 247+16	MBTO		BITUMINOUS	2.0
RT 247+32	ENTRANCE	PE	BITUMINOUS	1.5
LT 250+16	ENTRANCE	PE	AGGREGATE	3.8
RT 251+21	ENTRANCE	PE	BITUMINOUS	1.1
<b>TOTAL</b>				<b>421.0</b>

**GUTTER REMOVAL 44000400**

STATION	TO	STATION	FEET
LT 56+40		LT 60+40	400
LT 60+40		LT 60+45	5
RT 55+25		RT 60+40	515
RT 60+40		RT 60+45	5
<b>TOTAL</b>			<b>925</b>

**CLASS B PATCHES, TYPE II, 10" 44200970**

STATION	TYPE II, 10" NBL			TYPE II, 10" SBL		
	L	W	SQ.YD.	L	W	SQ.YD.
200+27	6	11	7.33	6	11	7.33
200+82	6	11	7.33	6	11	7.33
204+80	6	11	7.33	6	11	7.33
206+14	6	11	7.33	6	11	7.33
206+74	6	11	7.33	6	11	7.33
209+53	6	11	7.33	6	11	7.33
210+65	6	11	7.33	6	11	7.33
210+87				6	11	7.33
212+13	6	11	7.33	6	11	7.33
213+28	6	11	7.33	6	11	7.33
215+93	6	11	7.33	6	11	7.33
217+14	6	11	7.33	6	11	7.33
218+16	6	11	7.33	6	11	7.33
218+81	6	11	7.33	6	11	7.33
221+46	6	11	7.33	6	11	7.33
222+32	6	11	7.33	6	11	7.33
223+74	6	11	7.33	6	11	7.33
227+49	6	11	7.33	6	11	7.33
229+25	6	11	7.33	6	11	7.33
230+93	6	11	8.51			
234+11	6	11	7.33	6	11	7.33
235+44	6	11	7.33	6	11	7.33
236+45	6	11	7.33	6	11	7.33
237+07	6	11	7.33	6	11	7.33
237+73	6	11	7.33	6	11	7.33
238+39	6	11	7.33	6	11	7.33
244+81	6	11	7.33	6	11	7.33
249+53	6	11	7.33	6	11	7.33
Subtotal			199.09	197.91		
<b>TOTAL</b>			<b>397.0</b>			

**HOT-MIX ASPHALT SURFACE REMOVAL, 3/4" 44000152**

STATION	TO	STATION	SQ.YD.
76+17.25		169+86	24,984
200+00		202+00	512
202+00		248+86.67	11,457
TR 2300N (0+11 to 0+69)			238
<b>TOTAL</b>			<b>37,191</b>

**HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" 44000155**

STATION	TO	STATION	SQ.YD.
64+77.25		76+17.25	3040
249+36		251+70.57	574
ROSE HILL			38
BOAT CLUB RD.			27
0+69 (2300N)		0+85.5 (2300N)	20
<b>TOTAL</b>			<b>3,699</b>

Prepared by: Vermilion County Highway Dept. 2732 Batestown Road Oakwood, Illinois 61858	<b>DENMARK RD. (C.H. 20)</b> <b>2009 RESURFACING</b> <b>SECTION 07-00160-00-RS</b>	SHEET 8
		OF 71
		June 29, 2009