

ROUTE NO.	DISTRICT	COUNTY	SHEET NO.	SHEET TOTAL
FAS 496 *		Vermilion	18	3
FED. ROAD DIST. NO.	S.L. NO.	FED. AID PROJ. SECT.		

SCHEDULE OF QUANTITIES - VERM. SEC 97-00141-00-BR

44000153

HOT-MIX ASPHALT SURFACE REMOVAL, 1"		
LOCATION		SQ YD
STA 10+71.98 TO STA 11+75		115
TOTAL		115

44000157

HOT-MIX ASPHALT SURFACE REMOVAL, 2"		
LOCATION		SQ YD
STA 9+00 TO STA 9+28.03		31
STA 11+75 TO STA 12+25		56
TOTAL		87

44000161

HOT-MIX ASPHALT SURFACE REMOVAL, 3"		
LOCATION		SQ YD
STA 8+50 TO STA 9+00		56
STA 12+25 TO STA 12+50		28
TOTAL		84

40600100

BITUMINOUS MATERIALS (PRIME COAT)		
LOCATION		GAL
STA 8+50.00 TO STA 9+28.03		49
STA 10+71.98 TO STA 12+50.00		111
TOTAL		160

40600300

AGGREGATE (PRIME COAT)		
LOCATION		TONS
STA 8+50.00 TO STA 9+28.03		0.07
STA 10+71.98 TO STA 12+50.00		0.16
TOTAL		0.23

40603080

HMA BC IL-19.0 N50		
LOCATION		TONS
STA 8+50.00 TO STA 9+28.03		14
STA 10+71.98 TO STA 12+50.00		38
TOTAL		52

40603310

HMA SC "C" N50		
LOCATION		TONS
STA 8+50.00 TO STA 9+28.03		10.8
STA 10+71.98 TO STA 12+50.00		25.2
TOTAL		36

35100100

AGGREGATE BASE COURSE, TYPE A		
LOCATION		TONS
STA 8+50.00 TO STA 9+28.03		14.7
STA 10+71.98 TO STA 12+50.00		23.3
TOTAL		38

48100700

AGGREGATE SHOULDERS, TYPE A 8"		
LOCATION		SQ. YDS.
STA 8+50.00 TO STA 9+28.03		34.7
STA 10+71.98 TO STA 12+50.00		79.3
TOTAL		114

63000003

STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FT POSTS		
LOCATION		FOOT
STA 9+19.96 TO STA 9+19.96 LT		100
STA 7+34.04 TO STA 9+09.04 RT		175
STA 10+90.96 TO STA 12+79.46 LT		188
STA 10+80.04 TO STA 12+05.04 RT		125
TOTAL		588

63300725

STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)		
LOCATION		FOOT
STA 8+08 TO STA 8+19.5 RT		13
TOTAL		13

63100045

TRAFFIC BARRIER TERMINAL, TYPE 2		
LOCATION		EACH
STA 8+01.3 TO STA 8+08.4 LT		1
STA 12+05.04 TO STA 12+17.54 RT		1
TOTAL		2

63100075

TRAFFIC BARRIER TERMINAL, TYPE 5A		
LOCATION		EACH
STA 9+19.96 TO STA 9+33.21 LT		1
STA 9+09.04 TO STA 9+22.29 RT		1
STA 10+77.71 TO STA 10+90.96 LT		1
STA 10+66.79 TO STA 10+80.04 RT		1
TOTAL		4

LR631020

TRAFFIC BARRIER TERMINAL, TYPE 1		
LOCATION		EACH
STA 7+09.04 TO STA 7+34.04 RT		1
STA 12+65.96 TO STA 12+90.96 LT		1
TOTAL		2

DSGN	K.J. Hoffmann				
DR	K.J. Hoffmann				
CHK	J.P. Wolf				
APVD	J.A. Fraenhoffer	NO.	DATE	REVISION	BY

FRAUENHOFFER

Fraenhoffer and Associates, P.C. Consulting Engineers
3002 Crossing Court Champaign, IL 61822 217-351-6268

SCHEDULE OF QUANTITIES

FAS 496 (C.H. 14) OVER MIDDLE BRANCH OF N. FORK
SEC. 97-00141-00-BR
VERMILION COUNTY

SHEET 3

DWG NO. 97051500.dgn
DATE APR 2009
PROJ NO. 97051