

X-028-2A

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY J000-2A	STRUCTURE 057-7834
△ 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	2	
△ 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	1	
△ 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	1	
△ 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1	1	
△ * 87704080	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT. (SPECIAL)	EACH	1	1	
△ 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9	9	
△ 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3	3	
△ 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	45	45	
△ 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6	6	
△ 88100200	PEDESTRIAN SIGNAL HEAD, 1-FACE, BRACKET MOUNTED	EACH	2	2	
△ 88100400	PEDESTRIAN SIGNAL HEAD, 2-FACE, BRACKET MOUNTED	EACH	3	3	
△ 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	6	6	
△ 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1500	1500	
△ * 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	6	6	
△ * 89502380	REMOVE EXISTING HANDHOLE	EACH	2	2	
△ 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6	6	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
△ * Z0067700	STEEL CASINGS 20"	FOOT	148	148	
* LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	2050	2050	
△ * XX001490	GATE VALVES, 8"	EACH	2	2	
△ * XX002094	REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT	L SUM	1	1	
* XX002118	STORM SEWER, DUCTILE IRON 12 INCH	FOOT	140	140	

* SEE SPECIAL PROVISIONS

X028-2A

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY J000-2A	STRUCTURE 057-7834
△ * XX002982	GATE VALVES, 6"	EACH	2	2	
△ * XX003526	DUCTILE IRON WATER MAIN FITTING 8" X 6" REDUCER	EACH	2	2	
△ * XX003539	DUCTILE IRON WATER MAIN FITTING 8" X 6" TEE	EACH	1	1	
△ * XX003544	DUCTILE IRON WATER MAIN FITTINGS 6" 90 DEGREE BEND	EACH	1	1	
△ * X0469600	CONNECTION TO EXISTING WATERMAIN	EACH	2	2	
* XX004812	VIDEO TAPING OF SEWERS	FOOT	900	900	
△ * XX006168	SAMPLING TAP	EACH	2	2	
△ XX006228	RESTRAINED JOINT 6"	EACH	6	6	
△ * X0250215	PHOTOCELL CONTROL SYSTEM	EACH	1	1	
△ * XX007027	TRENCH BACKFILL, WATERMAIN	CU YD	260	260	
△ * X0323172	DUCTILE IRON WATER MAIN BEND, 45 DEGREE, 8 INCHES	EACH	4	4	
△ * X0323200	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	120	120	
△ * X0323363	ELECTRIC CABLE IN CONDUIT, NO. 12 3/C	FOOT	405	405	
△ * X0323840	WATER MAIN LINE STOP 6"	EACH	2	2	
△ * X0324932	DUCTILE IRON WATERMAIN 8" IN STEEL CASING	FOOT	150	150	
△ * X0325352	PIPE SUPPORT	EACH	1	1	
* X6020076	INLETS, SPECIAL, WITH SPECIAL FRAME AND GRATE	EACH	9	9	
△ * X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	345	345	

* SEE SPECIAL PROVISIONS

△ SPECIALTY ITEMS

DESIGNED - JDA	REVISED - 09/02/09
DRAWN - DRR	REVISED -
CHECKED - PJM	REVISED -
DATE - 07/22/09	REVISED -

TOWN OF NORMAL

SUMMARY OF QUANTITIES

VIRGINIA AVENUE OVER SUGAR CREEK
SECTION 04-00226-00-BR
MCLEAN, COUNTY

F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6356	04-00226-00-BR	MCLEAN	52	5
S.N. 057-7834		CONTRACT NO. 91416		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 5 OF 52 SHEETS STA. TO STA.