

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6999	08-00330-01-PV	VERMILION	77	11
VOORHEES STREET				
CONTRACT NO. 91417				

DISTRICT 5 GENERAL NOTES

- G.N.-100**
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.
- G.N.-105.09A**
ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)
- G.N.-201**
TREES THAT INTERFERE WITH THE CONSTRUCTION OPERATIONS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER. ANY TREE DUE TO ITS LOCATION AND DEEMED SUITABLE FOR SAVING BY THE ENGINEER SHALL BE PROTECTED OPERATIONS DURING CLEARING AND SUBSEQUENT CONSTRUCTION
- G.N.-202**
GRADING SHALL BE DONE BY HAND AROUND LIGHT POLES, UTILITY POLES, SIGN POSTS, SHRUBS, TREES OR OTHER NATURAL OR MAN-MADE OBJECTS WHERE SHALLOW FILLS OR CUTS ARE ADJACENT TO THE ITEMS. IT IS THE INTENT THAT THE LIMITS OF CONSTRUCTION BE SUCH AS TO PRESERVE IN THE ORIGINAL STATE AS MUCH AREA OF TEMPORARY EASEMENTS AS POSSIBLE. THE DECISION AS TO ITEMS TO REMAIN IN PLACE SHALL BE AS DIRECTED BY THE ENGINEER.
- THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- G.N.-205 - SPL.**
BENCHING PROCEDURES SHALL BE USED IN AREAS WHERE EXISTING EMBANKMENTS ARE WIDENED FOR THE PROPOSED WORK NEAR SN 092-6010. STEPS SHALL BE CUT INTO THE EXISTING EMBANKMENT SLOPES WITH ADEQUATE DIMENSIONS TO ALLOW FOR PROPER PLACEMENT AND COMPACTION OF THE PROPOSED EMBANKMENT.
- G.N.-250C SPL.**
SEEDING, CLASS 7 AND MULCH, METHOD 2 IS INCLUDED IN THIS CONTRACT TO SEED NEW EMBANKMENT DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE CLASS 7 SEEDING AND MULCH WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH SHOULDERS AT THE TIME OF THEIR COMPLETION.
- G.N.-406**
THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.
- G.N.-406.05b**
ALL LEVELING BINDER OR BINDER SHALL BE GIVEN A FOG COAT OF PRIME BEFORE THE SURFACE COURSE IS PLACED WHEN DIRECTED BY THE ENGINEER.
- THE FOG COAT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER GALLON FOR BITUMINOUS MATERIAL (PRIME COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- G.N.-440B**
THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.
- THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- G.N.-442B -- PATCHING SCHEDULES**
THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.
- G.N.-542**
BEFORE ORDERING PIPE CULVERTS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR THE EXACT LENGTHS.
- G.N.-550**
BEFORE ORDERING STORM SEWERS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR THE EXACT LENGTHS.
- G.N.-667**
THE RESIDENT ENGINEER SHALL CONTACT THE PROGRAM DEVELOPMENT CHIEF OF SURVEYS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE FOR INSTRUCTION AS TO SETTING OF TEMPORARY OR PERMANENT TIES FOR CENTERLINE ALIGNMENT CONTROL SURVEY MARKERS (PC $\frac{1}{2}$ S, PT $\frac{1}{2}$ S, AND P1 $\frac{1}{2}$ S). PROJECT IMPLEMENTATION PERSONNEL WILL BE RESPONSIBLE FOR SETTING THESE MARKERS.

PROJECT SPECIFIC GENERAL NOTES

1. ALL UTILITIES, SCHOOL DISTRICTS, LOCAL POLICE, AND FIRE DEPARTMENTS SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.
2. NO WORK SHALL COMMENCE UNTIL THE PROPOSED TRAFFIC CONTROL IS APPROVED AND IN PLACE.
3. MAILBOXES SHALL REMAIN IN SERVICE AT ALL TIMES AND SHALL BE RELOCATED AS NECESSARY DURING CONSTRUCTION. FINAL LOCATION OF MAILBOX SHALL BE DETERMINED BY THE ENGINEER BUT SHOULD BE NEAR AS PRACTICAL TO ITS ORIGINAL LOCATION OR AS SHOWN ON THE PLANS.
4. THE CONTRACTOR SHALL DEVELOP A PLAN TO ACCOMPLISH THIS WORK AND MINIMIZE DISRUPTION OF ACCESS. THIS PLAN SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO THE START OF WORK.
5. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS LISTED ON THE COVER SHEET.
6. THE CONTRACTOR WILL BE REQUIRED TO COMPLY WITH STATE REGULATIONS REGARDING AIR, WATER, AND NOISE POLLUTION.
7. REMOVAL OF AGGREGATE DRIVEWAY MATERIAL AS REQUIRED IS INCLUDED IN THE COST OF DRIVEWAYS AND SIDEWALKS OF THE TYPE SPECIFIED.
8. ALL SAW CUTS FOR CONTROL JOINTS IN PORTLAND CEMENT CONCRETE ITEMS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COST OF THE PAY ITEM FOR WHICH THEY ARE NEEDED AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
9. UTILITIES SHOWN ARE AS REPORTED TO US AND AS INDICATED ON EXISTING UTILITY BASE MAPS AND REFERENCE DATA PROVIDED TO US. NO ATTEMPT HAS BEEN MADE TO EXCAVATE, UNCOVER, OR EXPOSE THESE FACILITIES. TO FIELD CHECK THE EXISTENCE, SIZE, DEPTH, CONDITION, CAPACITY OR EXACT LOCATION OF THESE UTILITIES. FOR ADDITIONAL INFORMATION CONTACT:

10. CITY OF DANVILLE
ENGINEERING DIVISION OF
THE PUBLIC WORKS DEPARTMENT
1155 E. VOORHEES STREET, SUITE A
DANVILLE, IL 61832
PHONE: 217-431-2384
FAX: 217-431-2237

SANITARY SEWERS, STORM SEWERS:
CITY OF DANVILLE SEWER DEPARTMENT
1155 E. VOORHEES STREET, SUITE A
DANVILLE, IL 61832
PHONE: 217-431-2384
FAX: 217-431-2237

WATER:
AQUA ILLINOIS WATER CO.
1300 WEST FAIRCHILD STREET
DANVILLE, IL 61832
PHONE: 217-442-3063
FAX: 217-442-0178

POWER:
AMERENIP
1112 WEST ANTHONY DRIVE
URBANA, IL 61803-7070
PHONE: 1-800-755-5000
FAX: 217-424-7007

GAS:
AMERENIP
2460 NORTH JASPER STREET
DECATUR, IL 62526
PHONE: 800-755-5000
FAX: 217-425-4151

CABLE TELEVISION:
INSIGHT COMMUNICATIONS
806 1/2 EAST MAIN STREET
DANVILLE, IL 61832
PHONE: 217-443-2941
FAX: 217-443-3907


TELEPHONE:
SBC
201 S NEIL ST
CHAMPAIGN, IL 61820
PHONE: 217-398-7979
FAX: 217-398-7991

FIRE DEPARTMENT
DANVILLE FIRE DEPARTMENT
1111 NORTH GRINNIN STREET
DANVILLE, IL 61832
PHONE: 217-431-2350
FAX: 217-431-2359
EMERGENCY: 911

DEPARTMENT OF ENGINEERING
DANVILLE, IL. R. DAVID SCHNELLE, CITY ENGINEER
VOORHEES ST IMPROVEMENT PHASE I
GENERAL NOTES

SCALE: 1:XX
DATE: 7/24/2009

DRAWN BY:
CHECKED BY:



X:\Projects\City\Current\08-00330-00PV-Voorhees\CIVIL\DWG\GENNOTES.dwg