

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 7015	08-00026-00-RS	VERMILION	21	5
STA.		TO STA.		
F.H.W.A. REC.		ILLINOIS PROJECT NO. ARA-5016 (039)		

SUMMARY OF QUANTITIES

CODE #	ITEM NAME	UNIT	QUANTITIES
40600100	BITUMINOUS MATERIAL (PRIME COAT)	GALLON	1,000.0
40600300	AGGREGATE (PRIME COAT)	TON	21.4
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	790.0
* 40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,323.8
40600990	TEMPORARY RAMP	SQ YD	621.8
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,200.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	87.5
40800030	AGGREGATE (PRIME COAT)	TON	1.9
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	105.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,600.0
* 42400800	DETECTABLE WARNINGS	SQ FT	420.0
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,229.4
44000600	SIDEWALK REMOVAL	SQ FT	1,600.0
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	7.9
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	60.3
48101200	AGGREGATE SHOULDERS, TYPE B	TON	140.0
60255500	MANHOLES TO BE ADJUSTED	EACH	11.0
67100100	MOBILIZATION	L SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	888.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	148.0
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,699.0
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	834.0
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	240.0
* Δ 81400115	HANDHOLE TO BE ADJUSTED	EACH	1.0
* 44001700	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	265.0
* XX006859	VALVES TO BE ADJUSTED	EACH	21.0
* Z0001400	ANTI-STRIP ADDITIVE	UNIT	1,236.0
* Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0
* Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	1.0

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

PLAN

DATE _____ BY _____

SURVEYED _____

GRADES CHECKED _____

PLOTTED _____

NOTE BOOK NO. _____

RT. OF WAY CHECKED _____

PROFILE

DATE _____ BY _____

SURVEYED _____

GRADES CHECKED _____

PLOTTED _____

NOTE BOOK NO. _____

STRUCTURE NOTATIONS CHECKED _____