

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 7015	08-00026-00-RS	VERMILION	21	6
STA.		TO STA.		
F.H.W.A. REG.		ILLINOIS PROJECT NO. ARA-5016 (039)		

SCHEDULES OF QUANTITIES

44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
STATION TO STATION		SQ YD	
RT 20+00	23+05	203.2	
LT 20+00	23+05	203.5	
RT 23+61	35+80	819.7	
LT 23+61	35+80	812.7	
RT 37+94	46+87	595.2	
LT 37+94	46+87	595.1	
TOTAL		3229.4	

NOTE: MILL 6" WIDE AT EDGE
2" AT EOP, 0" AT 6'

44000600 & 42400100 SIDEWALK REMOVAL AND PCC SIDEWALK, 4"			42400800 DETECTABLE WARNINGS	
STATION	SQ FT		SQ FT	
RT 17+47	21.8		7.1	
RT 17+67	13.2		6.0	
LT 25+11	30.0		7.2	
LT 25+20	53.3		8.0	
LT 25+58	40.4		7.8	
LT 25+66	69.3		9.5	
LT 28+61	51.2		9.0	
LT 28+69	34.9		7.5	
RT 28+89	64.6		20.4	
LT 29+06	40.1		7.9	
RT 29+26	70.7		27.0	
LT 31+40	27.2		13.0	
LT 31+80	31.0		13.2	
RT 33+15	53.7		19.1	
RT 33+51	41.1		19.4	
LT 33+55	112.7		53.2	
RT 38+17	37.2		10.8	
RT 38+60	114.4		8.6	
RT 39+77	35.9		10.7	
LT 40+04	18.2		8.9	
RT 40+16	37.6		10.9	
LT 40+52	20.1		9.8	
LT 43+24	20.3		11.0	
LT 43+62	39.6		12.2	
RT 46+02	22.7		11.7	
LT 46+46	27.9		13.3	
RT 46+60	102.3		8.8	
LT 46+83	39.6		8.9	
RT 50+71	58.3		10.8	
RT 53+92	114.1		8.0	
CONTINGENCY	156.6		40.4	
TOTAL		1600.0	420.0	

XX003560 CURB AND GUTTER REMOVAL AND REPLACEMENT		
STATION	TYPE	FOOT
LT 25+12	B-6.12	6.1
LT 25+25	B-6.12	6.5
LT 25+57	B-6.12	28.4
LT 28+62	B-6.12	7.7
LT 28+72	B-6.12	6.2
RT 28+91	B-6.12	24.6
LT 29+01	B-6.12	6.3
RT 29+25	B-6.12	21.2
LT 31+41	B-6.12	14.4
LT 31+78	B-6.12	14.1
RT 33+15	B-6.12	15.2
LT 33+48	B-6.12	34.3
RT 33+54	B-6.18	18.9
LT 43+26	B-6.12	12.4
LT 43+60	B-6.12	15.0
CONTINGENCY		33.7
TOTAL		265.0

NOTE: CURB AND GUTTER SHOULD MATCH ADJACENT TYPE. TYPE IS PROVIDED FOR INFORMATION ONLY.

XX006859 VALVES TO BE ADJUSTED		
STATION	EACH	
RT 17+63	1	
LT 21+85	1	
RT 22+73	1	
LT 25+14	1	
LT 29+01	1	
LT 31+35	1	
LT 32+55	1	
LT 33+31	1	
LT 34+44	1	
LT 34+51	1	
LT 34+55	1	
RT 34+57	1	
LT 34+99	1	
LT 35+01	1	
LT 38+13	1	
RT 38+32	1	
LT 40+16	1	
LT 43+36	1	
RT 46+25	1	
LT 49+14	1	
RT 54+08	1	
TOTAL		21

78000400 THERMOPLASTIC PAVEMENT MARKING LINE 6"			
LOCATION	TYPE	WHITE FOOT	
S RANCH	20' RT XW	18	
S RANCH	26' RT XW	14	
COOK	32' LT XW	23	
COOK	38' LT XW	26	
N SCOTT	28' LT XW	29	
N SCOTT	34' LT XW	26	
S SCOTT	17' RT XW	38	
S SCOTT	23' RT XW	26	
BOWMAN	18' LT XW	37	
BOWMAN	23' LT XW	27	
N WEST	17' LT XW	43	
N WEST	23' LT XW	33	
S WEST	17' RT XW	37	
S WEST	22' RT XW	27	
BROOKS	17' RT XW	38	
BROOKS	22' RT XW	31	
S WASHINGTON	17' RT XW	27	
S WASHINGTON	22' RT XW	24	
N WASHINGTON	18' LT XW	41	
N WASHINGTON	22' LT XW	34	
ADAMS	17' LT XW	30	
ADAMS	21' LT XW	21	
WALNUT	19' RT XW	45	
WALNUT	24' RT XW	35	
JEFFERSON	16' LT XW	34	
JEFFERSON	20' LT XW	24	
BRIDGETT	16' RT XW	25	
BRIDGETT	21' RT XW	21	
TOTAL		834	

NOTE: "XW" MEANS CROSSWALK

78000100 THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS		
LOCATION	TYPE	WHITE SQ FT
RR 22+02	6' R	3.6
RR 22+02	6' R	3.6
RR 22+02	20' X	54.0
RR 24+67	6' R	3.6
RR 24+67	6' R	3.6
RR 24+67	20' X	54.0
TOTAL		122.4

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
STATION TO STATION		SQ YD
10+00	10+60	117.9
N. RANCH ST.		58.4
S. RANCH ST.		40.5
RR 23+05	23+21	55.0
RR 23+51	23+61	35.7
COOK ST.		91.2
N. SCOTT ST.		82.4
S. SCOTT ST.		50.9
BOWMAN ST.		52.0
N. WEST ST.		36.8
S. WEST ST.		42.5
35+80	36+10	110.6
37+64	37+94	101.3
BROOKS ST.		54.6
S WASHINGTON AVE.		21.5
N WASHINGTON AVE.		36.6
ADAMS ST.		32.7
WALNUT ST.		80.5
JEFFERSON ST.		49.2
BRIDGETT ST.		50.3
NICHOLS ST.		50.6
55+84	56+14	72.5
TOTAL		1323.8

60255500 MANHOLES TO BE ADJUSTED		
STATION	EACH	
RT 17+65	1	
LT 22+53	1	
LT 25+60	1	
LT 33+19	1	
RT 33+93	1	
RT 46+28	1	
LT 46+55	1	
LT 46+76	1	
RT 46+82	1	
RT 50+54	1	
RT 54+15	1	
TOTAL		11

78000200 THERMOPLASTIC PAVEMENT MARKING LINE 4"				
STATION TO STATION	TYPE	WHITE FOOT	YELLOW FOOT	
10+00	16+19	LT EDGE	619	-
10+00	17+40	RT EDGE	740	-
16+62	19+70	LT EDGE	308	
17+77	19+76	RT EDGE	199	
10+00	20+00	CENTER SD	-	250
20+00	36+10	CENTER SD	-	403
37+65	46+87	CENTER SD	-	231
46+87	55+95	CENTER SD	-	227
46+87	50+29	RT EDGE	342	-
46+96	55+95	LT EDGE	899	-
50+66	53+86	RT EDGE	320	
54+33	55+95	RT EDGE	162	
SUB-TOTAL			3589	1110
TOTAL			4699	

NOTE: "SD" = 10-40 SKIP-DASH

78000650 THERMOPLASTIC PAVEMENT MARKING LINE 24"		
LOCATION	WHITE FOOT	
N RANCH	11	
S RANCH	7	
RR 21+77	12	
RR 22+27	12	
RR 23+17	12	
RR 23+52	12	
RR 24+42	12	
RR 24+92	12	
COOK	12	
N SCOTT	10	
S SCOTT	10	
BOWMAN	9	
N WEST	13	
S WEST	10	
BROOKS	15	
S WASHINGTON	8	
N WASHINGTON	14	
ADAMS	9	
WALNUT	13	
JEFFERSON	9	
BRIDGETT	9	
NICHOLS	9	
TOTAL		240

Z0051500 REMOVING AND RESETTING STREET SIGNS		
STATION	EACH	
LT 33+53	1	
TOTAL		1

PLAN
SURVEYED
PLOTTED
NOTE BOOK
ALIGNED
CHECKED
RT. OF WAY
NO.

PROFILE
SURVEYED
PLOTTED
NOTE BOOK
GRADES
CHECKED
B.M.'S NOTED
STRUCTURE NOTATIONS
CHK'D
NO.