

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	PIATT	53	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CULVERT SCHEDULE

LOCATION	INLETS TB T8G PRCFST (60240301)	INLETS TA T8G (60236200)	CLASS D, TYPE 1			END SECTIONS			TRENCH BACKFILL (20800150)	FILLING EXIST CULVERTS (Z0023600)	CULVERT TO BE CLEANED (Z0014700)	CLASS A, TYPE 1, 30" (542A0235)	CONCRETE COLLAR (54248510)	REINFORCEMENT BARS (50800105)	EXPANSION BOLTS (54002070)
			15"	18"	18" ERS	15"	18"	18" ERS							
			(542D0220)	(542D0223)	(542D5473)	(54213450)	(54213453)	(54214293)							
EACH	EACH	FOOT	FOOT	FOOT	EACH	EACH	EACH	CU YD	EACH	EACH	FOOT	CU YD	POUND	EACH	
STA. 12+38 RT			50			2									
STA. 14+14 RT			50			2									
STA. 16+20 RT			200			1									
STA. 16+25 LT			180			1									
STA. 18+05 LT	1														
STA. 18+07 LT			190			1									
STA. 18+20 RT	1														
STA. 18+22 RT			335			1									
STA. 22+05 RT										15"Ø, 267' LONG					
STA. 26+41 LT			35			2									
STA. 26+90 RT		1													
STA. 26+92 RT			60			1		11							
STA. 28+75 RT				245			1								
STA. 31+20 RT	1														
STA. 31+22 RT				20											
STA. 44+98										2' SQ, 65' LONG	17	0.5	30	8	
STA. 63+83 RT				90			2								
STA. 66+14 RT															
STA. 68+98 RT										18"Ø, 105' LONG					
STA. 73+50 LT					375			2							
STA. 76+47 RT				50			2								
STA. 77+96									1.5'X2', 32' LONG						
STA. 82+31 RT										15"Ø, 41' LONG					
STA. 83+19 RT										15"Ø, 35' LONG					
TOTALS	3	1	1100	405	375	11	5	2	11	1	5	17	0.5	30	8

\*75-YEAR MINIMUM SERVICE LIFE

**ESCA**  
CONSULTANTS, INC.

DESIGNED BY:	ELH	01/09
DRAWN BY:	cj/HAS	01/09
CHECKED BY:	ELH	07/09
APPROVED BY:	RDP	07/09

SCHEDULES OF QUANTITIES  
FAS 535 (SHADY REST ROAD)  
SECTION 08-00115-01-RS  
PIATT COUNTY