

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION CU. YD.	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE* CU. YD.	EMBANKMENT CU. YD.	EARTHWORK BALANCE** WASTE (+) OR SHORTAGE (-) CU. YD.
STA. 8+00.00 TO STA. 9+66.19	71	53	107	-54
STA. 10+30.53 TO STA. 13+20.53	38	28	532	-504
TOTAL	109	81	639	-558

*25% SHRINKAGE **FURNISHED EXCAVATION

TREE REMOVAL SCHEDULE	
LOCATION	ACRES
LT., STA. 8+00.00 TO STA. 10+60.00	0.2
RT., STA. 8+00.00 TO STA. 9+25.00	0.1
TOTAL	0.3

DATE	BY

DATE	BY

08/12/2009
 PLOT DATE = #DATE*
 FILE NAME = #FILE#*
 PLOT SCALE = #SCALE*
 USER NAME = #USER#

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TR 140	07-11120-00-BR	FAYETTE	10	3
STA. 4+00.00 TO STA. 15+00.00		ILLINOIS		

